

THE UNITED STATES PATENT AND TRADEMARK OFFICE

ASSISTANT COMMISSIONER FOR PATENTS
Washington, D.C. 20231

Prior Application: Art Unit: 3731
Examiner: D. Reip

SIR: This is a request for filing a

☐ Continuation ☐ Continuation-in-Part ☒ Divisional Application under 37 C.F.R. § 1.53(b) of pending prior application Serial No. 09/022,293 filed February 11, 1998 of Gary K. Michelson for Anterior Cervical Plating System, Instrumentation, And Method Of Installation

1. ☒ Enclosed is a complete copy of the prior application including the oath or Declaration and drawings, if any, as originally filed. I hereby verify that the attached papers are a true copy of prior application Serial No. 09/022,293 as originally filed on February 11, 1998.
2. ☐ Enclosed is a substitute specification under 37 C.F.R. § 1.125.
3. ☒ Cancel Claims 1-199 and 291-537.
4. ☐ A Preliminary Amendment is enclosed.
5. ☒ The filing fee is calculated on the basis of the claims existing in the prior application as amended at 3 and 4 above.

Basic Application Filing Fee					\$690	\$ 690.00
	Number of Claims		Basic	Extra Claims		
Total Claims	91	-	20	71	x \$18	1,278.00
Independent Claims	3	-	3	0	x \$78	0
[] Presentation of Multiple Dep. Claim(s)					+\$260	0
Subtotal						\$ 1,968.00
Reduction by 1/2 if small entity						- 0
TOTAL APPLICATION FILING FEE						\$ 1,968.00

jc836 U.S. PRO
09/618566

6. ☒ A check in the amount of \$1,968.00 to cover the filing fee is enclosed.
7. ☒ The Commissioner is hereby authorized to charge any fees which may be required including fees due under 37 C.F.R. § 1.16 and any other fees due under 37 C.F.R. § 1.17, or credit any overpayment during the pendency of this application to Deposit Account No. 50-1066.
8. ☒ Amend the specification by inserting before the first line, the sentence:

--This is a ☐ continuation ☒ divisional of application Serial No. 09/022,293, filed February 11, 1998, and claims the benefit of U.S. provisional application no. 60/037,139 filed February 11, 1997, incorporated herein by reference.--

9. ☐ New formal drawings are enclosed.
10. ☐ The prior application is assigned of record to: _____
11. ☐ Priority of application Serial No. _____, filed on _____ in _____ (country) is claimed under 35 U.S.C. § 119. A certified copy
☐ is enclosed or ☐ is on file in the prior application.
12. ☐ A verified statement claiming small entity status
☐ is enclosed or ☐ is on file in the prior application.
13. ☒ The power of attorney in the prior application is to at least one of the following: MARTIN & FERRARO, LLP; Thomas H. Martin, Reg. No. 34,383; Amedeo F. Ferraro, Reg. No. 37,129; and Todd M. Martin, Reg. No. 42,844.
14. ☐ The power appears in the original declaration of the prior application.
15. ☒ A new Revocation of Original Power of Attorney and Grant of New Power of Attorney is enclosed.
16. ☒ Please address all correspondence to:

Customer No. 22882
 MARTIN & FERRARO, LLP
 14500 Avion Parkway, Suite 300
 Chantilly, Virginia 20151-1101

**22882**

PATENT TRADEMARK OFFICE

00220"9952960

17. ☐ Recognize as associate attorney _____
(name, address & Reg. No.)
18. ☒ Also enclosed is Information Disclosure Statement Under 37 C.F.R.
§ 1.97(b) with Form PTO-1449 and five documents

PETITION FOR EXTENSION. If any extension of time is necessary for the filing of this application, including any extension in the parent application, serial no. 09/022,293, filed February 11, 1998, for the purpose of maintaining copendency between the parent application and this application, and such extension has not otherwise been requested, such an extension is hereby requested, and the Commissioner is authorized to charge necessary fees for such an extension to our Deposit Account No.50-1066. A duplicate copy of this paper is enclosed for use in charging the deposit account.

Respectfully submitted,

MARTIN & FERRARO, LLP

Dated: July 17, 2000

By: Thomas H. Martin
Thomas H. Martin
Registration No. 34,383
14500 Avion Parkway, Suite 300
Chantilly, VA 20151-1101
Telephone: (703) 679-9300
Facsimile: (703) 679-9303

002720 99587960

PATENT APPLICATION
FOR AN
ANTERIOR CERVICAL PLATING SYSTEM, INSTRUMENTATION,
AND METHOD OF INSTALLATION
BY
GARY K. MICHELSON

0913556.071700

BACKGROUND OF THE INVENTION

1. Related Applications

This application claims priority of Application Serial No. 60/037,139 filed February 11, 1997, incorporated herein by reference. Application Serial No. 08/____,____, (Attorney Docket No. P-13408) filed February 11, 1998, and titled SKELETAL PLATING SYSTEM is incorporated herein by reference.

2. Field of the Invention

The present invention relates generally to implants, method, and instrumentation for fusion of the human cervical spine from the anterior aspect, and in particular to plate systems for aligning and maintaining adjacent cervical vertebrae in a selected spatial relationship during spinal fusion of those vertebrae.

3. Description of the Related Art

It is current practice in the art to use cervical plating systems for this purpose. Such systems are composed essentially of plates and screws for aligning and holding vertebrae in a desired position relative to one another. The earliest such devices consisted of stainless steel plates and screws and required that the screws passed entirely through the vertebrae and into the spinal canal in order to engage the strong

bone tissue (the posterior cortex) of the vertebral bodies. This required the ability to observe or visualize this area radiographically, which is not always possible, especially in the lower cervical spine where the vertebrae may be hidden radiographically by the shoulders.

In order to form holes in the vertebral bodies for insertion of each screw, a drilling operation was performed, followed by a tapping operation. Each of these operations involved the passage of an instrument entirely through the associated vertebral body and into the spinal column. Thus, these instruments come into close proximity to the spinal cord and the dural sac which are in close proximity to the back surfaces of the vertebral bodies. Any procedure which introduces an object into the spinal canal presents serious risks which are of concern to the surgeon.

The conventional technique of forming a bone screw receiving hole in vertebral bodies by drilling has a number of significant disadvantages. For example, drilling removes bone material, leaving a void and resulting in a loss of bone material. Drilling also causes microfracturing of the bone at the drill bit-bone interface and the resulting fracture lines tend to propagate in directions perpendicular to the wall of the hole. More specifically, the bone material is essentially a type of ceramic which exhibits a brittle pattern of fracture formation

and propagation in response to drilling. Furthermore, drilling generates heat which can result in thermal necrosis of the bone material precisely at the interface between the bone and a subsequently installed screw, where necrosis is most harmful. Any bone which does experience necrosis will subsequently be resorbed by the body as part of the bone repair process and this can lead to the loosening of the screw.

Another problem with drilling is that the path of the drill bit is difficult to control and since the drill bit operates by rotation, it can wind up soft tissue about the associated plate. In addition, unless great care is taken, the drill bit may be driven significantly past the posterior cortex and cause irreparable harm within the spinal canal. Finally, a drill bit may bind and fracture within the vertebral body and can then cause serious injury as the still rotating portion of the drill bit passes into the wound, while the portion of the bit which has broken off may either protrude dangerously from the vertebral body or may be broken off flush with the upper surface of the body so as to be irretrievably embedded therein. In any event, the steps that must be taken to retrieve the broken-off portion of a drill bit will inevitably prolong and complicate the surgical procedure.

In known plating systems, there have been problems with loosening and failure of the hardware, breakage of the screws and

plates, and backing out of screws into the patient's throat area. These occurrences generally require further surgical procedures to replace the broken parts or the plates and screws entirely, and to repair any damage that may have been caused.

Other problems which have been encountered with known systems result from the failure of the screws to achieve a sufficient purchase in the bone and the stripping of the screws.

Also, the use of the known plating systems may result in a loss of lordosis, which is the normal curve of the cervical spine when viewed from the side.

Known plating systems additionally experience problems in connection with those procedures where bone grafts are placed between vertebral bodies to achieve an interbody fusion which heals by a process called "creeping substitution". In this process, bone at the interface between the graft and a vertebra is removed by a biological process which involves the production of powerful acids and enzymes, as a prelude to invasion of the interface by living tissue and the deposition, or growth, of new bone. While the plates allow for proper alignment of the vertebrae and their rigid fixation, they can therefore, at the same time unfortunately, hold the vertebrae apart while the resorption phase of the creeping substitution process forms gaps in the bone at the fusion site with the result that the desired fusion does not occur. Such failure is known as pseudoarthrosis.

When such a failure occurs, the hardware itself will usually break or become loosened from the spine, thus requiring a further surgical procedure to remove the broken components and another surgical procedure to again attempt fusion.

In response to the problems described above, a second generation of plating systems has been developed and/or proposed. These include a system disclosed in U.S. Patent Nos. 5,364,399 to Lowery and 5,423,826 to Morscher, as well as cervical spine locking plating systems offered by SYNTHES Spine, the DANEK ORION plate, the CODMAN SHURTLEFF plate, and the SMITH NEPHEW RICHARDS plate, among others. The systems' forming members of this second generation have a number of common properties. They are all made of either a titanium alloy or pure titanium rather than stainless steel, to minimize adverse tissue reactions and are MRI compatible, which stainless steel is not. The screws and the plates have been given increased thickness in order to achieve increased strength. The screws have larger diameters to improve their purchase without requiring that they engage the posterior cortex of the vertebral bodies. Some mild longitudinal contouring of the plates is employed to allow for some lordosis, and/or limited transverse contouring to better follow the generally curved aspect of the front of the vertebral bodies. Mechanisms are employed for securing the vertebral bone screws to their associated plates in a manner to prevent the screws from

backing out. While this second generation of plating systems represents a significant improvement over earlier systems, certain existing problems persist, while new problems have been created.

For example, since the screws no longer extend into the posterior cortex, it is common for the threads in the tapped screw hole to become stripped and for the screws to fail to gain a suitable purchase. In addition, screw breakage continues to be experienced and occurs most commonly at the junction of the screw to the posterior aspect of the plate. The screws employed in both the SYNTHES system and the SMITH NEPHEW RICHARDS system are particularly vulnerable to this problem because those screws are hollow at the level where they attach to the plate to permit the internal reception of locking screws.

In an attempt to prevent screw to plate junction breakage of the screw, more recent designs of screws have an increasing root diameter from tip to head, which thus far has resulted in a near useless stubby and blunt thread near the screw head with little holding power and little tactile feedback to the surgeon to signal the completion of tightening prior to stripping of the screw within the bone. Based on empiric studies testing these prior art screws, the use of a pretapped hole, rather than a self-tapping screw, was found to be preferred for pullout strength and thus these screws have not been self-tapping and

thus the screw holes must be pre-tapped. Since the thread cutting portion of a tap is necessarily sharp and rotated to work, there is a serious risk of damage to the surrounding soft tissues when it is used. This is compounded by the fact that the plates employed in these systems do not provide sufficient long axis contouring to make full allowance for lordosis and do not have sufficient transverse contouring to prevent rocking of the plate about its longitudinal axis and to conform to the anterior shape of the vertebral bodies, so that these plates do not prevent soft tissue from creeping in from the sides and beneath the screw holes thus exposing these tissues to damage by the drill and the tap. While it is possible, at the time of surgery, to make some change in the contouring of these plates, this is generally limited to contouring of the longitudinal axis and quite often causes distortion of the plate's bone screw holes and screw hole to plate junctions in a manner which has an adverse effect on the screw-plate interlock. Lack of proper contouring prevents these plates from having an optimally low profile relative to the spine.

In some of the second generation cervical plating systems, screw backout continues to occur, because these plates could not be designed to allow for the locking of all of the screws. Specifically, while the designers of these plates recognized the importance of securing the bone screws to the

plates, they were unable to lock all of the screws and had to settle for leaving some of the screws unlocked.

Furthermore, several of these second generation systems utilize tiny and delicate "watchmaker" parts to achieve interlocking. These parts are characterized by the need to engage them with particularly delicate small ended screw drivers. These interlocking components are easily rendered ineffective by any effort to alter the contours of a plate during surgery.

Despite the improvement of these second generation plating systems over the first problems, the problems still persist, the most important of which is pseudoarthroses, and particularly "distraction pseudoarthroses". Although these second generation plates have clearly led to an increase in fusion rate, when a failure to produce fusion occurs, it is generally accompanied by bone resorption along a line at the graft-to-vertebra junction, which can be seen on a radiograph.

In the case of the weak first generation plates and screws, the plates might hold the vertebrae apart, preventing fusion, but only until the hardware would break, relieving the distraction, and then allowing the fusion to occur. The second generation systems of plates are too strong to allow this to occur, thus requiring further surgical procedures for the correction of the pseudoarthroses.

Compression plates are well-known and are widely used

in orthopedic surgery for the stabilization of tubular bones, and sometimes also flat bones. Such plates may rely on some external compression means or may be self-compressing, relying on the ability of the screw head to slide within a ramped slot such that the tightening of the bone screws through the plate imparts a linear motion perpendicular to the screw axes. U.S. Patent No. 5,180,381 discloses an attempt to employ such a mechanism in connection with anterior spinal fixation.

However, it has been found that all of the proposed self-compressing plating systems have in common the need for a screw to engage both a proximal and a distal cortex, (bone casing of very dense bone material), so as to anchor the screw tip in a manner to allow the plate to move relative to the screw when tightened rather than allowing the plate to drag the screw off axis. However, as already discussed earlier herein, when a screw is to engage the posterior cortex of the vertebral body, it is necessary for the drill and the tap which form the screw hole, as well as the screw tip itself, to all enter the spinal canal, thereby exposing the spinal cord to damage.

While the system disclosed in U.S. Patent No. 5,180,381 avoids such danger by engaging the vertebral body end plate instead of the posterior vertebral body cortex, the path of the screw is of necessity quite short, so that there is very little opportunity for the screw threads to achieve additional purchase

within the vertebral body. It would therefore appear that to the extent that the device disclosed in U.S. Patent No. 5,180,380 is able to achieve its stated objectives, it would pull the front of the spine together more than the back and would not appear to compress the back of the vertebral bodies at all, thus producing an undesirable iatrogenic loss of the normal cervical lordosis. Such a situation is disruptive to the normal biomechanics of the cervical spine and potentially quite harmful.

The creation of compression between adjacent vertebrae would offer a number of advantages, including reduced distraction pseudoarthrosis, increased surface area of contact between the graft and vertebrae as slightly incongruent surfaces are forced together, increased osteogenic stimulation, since compressive loads stimulate bone formation, and increased fusion graft and spinal segment stability.

Among the new problems created by these second generation systems is a tendency for the small "watchmaker" parts used to lock the bone screws to the plate to fall off of the driver used for attaching those parts, or out of the associated plates and to become lost in the wound. In addition, these small parts are quite fragile and require specialized additional instruments for their insertion and/or manipulation.

Furthermore, incorrect bone screw placement relative to the axis of a plate hole may render the screw locking mechanism unworkable

or may cause sharp and jagged shavings of titanium to be formed as a locking screw is driven into contact with an improperly seated bone screw. The means for establishing bone screw to plate hole alignment and preparation are less than reliable. Furthermore, most of these second generation systems lack a reliable and effective means for positioning and holding the plate during attachment.

Specific features of various prior art systems will be summarized below.

The system disclosed in U.S. Patent Nos. 5,364,399 and 5,423,826, cited earlier herein, includes a thin stainless steel plate which allows for side-by-side or offset bicortical screw placement, the plate having a combination of screw holes and slots.

The "Acromed" system includes a titanium plate and screws which require bicortical screw placement. This system does not include any locking means for the bone screws.

The system disclosed in U.S. Patent No. 5,180,381 includes an "H" shaped plate having a combination of ramped slots and a hole which requires bicortical screw placement at a 45° angle to the plane of the plate. This patent discloses that this angular positioning is for the purpose of producing compression.

The SYNTHES Morscher plate system employs hollow, slotted screw heads. The screws are placed unicortically so that

the heads, when properly aligned, come to rest in the upper portion of the plate holes. The upper portion of each screw is internally threaded to receive a tiny screw which is screwed into the bone screw head in order to increase the interference fit between the bone screw head and the wall of the associated plate hole.

In the system disclosed in U.S. Patent Nos. 5,364,399 and 5,423,826, use is made of pairs of unicortical bone screws that may be locked in place at both ends of the associated plate by locking screws which have a small diameter shank and a large head. At each end of a plate two bone screws may be locked in place by a single locking screw which is situated between the bone screws. Generally, the plate is provided, between its two ends, with a diagonal slot or slots for receiving one or more additional screws, each additional screw being securable in a bone graft or a respective vertebra which is spanned by the plate. There is no locking screw associated with these intermediate bone screws to lock the bone screws to the plate.

The Codman Shurtleff plating system utilizes the side of a preinstalled rivet having a head rotatable to press against the side of the head of a bone screw so as to secure that one screw to the plate. The plates of this system also are provided with holes for receiving intermediate screws, but these screws are not associated with any locking means.

While the designers of the last-mentioned systems recognized the importance of locking the bone screws in position on their associated plates, they did not provide for any locking of the intermediate bone screws in their associated holes.

In an earlier version of the Codman Shurtleff system, the locking mechanism was a lever pivotable about a shaft passing entirely through the plate and then flared so as to retain the shaft within the plate. The lever was rotated after the bone screw had been inserted to engage the head of the bone screw and thus secure the bone screw to the plate.

Based on a consideration of the features of all of the known cervical plating systems, it appears that there remains a need for an improved system having the following combination of features:

- 1) The plate should be sufficiently strong to perform its intended function without mechanical failure;
- 2) The plate should be preformed in three dimensions so as to anatomically conform in both the longitudinal and transverse planes to the anterior cervical spine;
- 3) The plate should be constructed so that all of the bone screws are generally perpendicular to the plate when viewed from the side, but pairs of

screws are highly convergent corresponding to any vertebral level when viewed from the bottom, or on end;

- 4) Each pair of screws engages in a respective vertebra and the high convergence of screws in a pair allows the length of the screws which engage the bone to be longer and still remain within that vertebra and provide a safer and stronger engagement with the vertebrae;
- 5) The system should include bone screws which are capable of achieving enhanced purchase within the bone of the vertebral body and without the need to penetrate the posterior vertebral cortex and enter the spinal canal;
- 6) Use should be made of a screw which is self-tapping, thereby eliminating the need for separate tapping steps;
- 7) A reliable means should be provided for engaging and manipulating the plate during installation;
- 8) The plate should be engageable with an instrument means which can reliably produce bone screw holes which are coaxial with the screw holes in the plate;
- 9) It should be possible to prepare the vertebral

bone to receive the bone screws so as to produce a stronger connection and a reduced danger of thread stripping by means of a pilot hole punch creating a pilot hole for the bone screws;

- 10) Alternatively to the use of a pilot hole punch, a relatively (compared to the overall root diameter of the screw) small diameter drill may be used to create the pilot hole.
- 11) Means should be provided for locking each and every bone screw in position relative to the plate, and the locking means should be of sufficient size and strength to reliably perform its intended functions;
- 12) Bone screw locking means should preferably be retainable by the plate prior to bone screw insertion, or should be reliably attachable to a driver to prevent any small parts from becoming loose in the wound; and
- 13) The system should be capable of effecting compression of the vertebral segments to be fused while maintaining and/or restoring lordosis.

OBJECTS OF THE INVENTION

It is an object of the present invention to provide an

improved anterior cervical plating system, installation instrumentation, and installation method which has the above described features and which avoids many of the shortcomings of previously known systems.

One object of the present invention is to provide a locking mechanism where a plurality of bone screws used for attaching the plate to the vertebrae can be easily and reliably locked in place at the same time by a single operation.

Another object of the present invention is to provide a vertebral plate in which the locking mechanisms for locking the bone screws may be pre-installed by the manufacturer prior to the insertion of the bone screws by the physician so that the physician does not have to attach the locking mechanism to the plate as a separate procedure during the operation.

Another object of the invention is to provide an anterior cervical plating system which allows for the intersegmental compression of the spinal segment (compression of the adjacent vertebrae and the fusion graft in the disc space between the adjacent vertebrae) in lordosis, and similarly, where desired, multisegmental compression.

A further object of the invention is to provide bone screws which provide for tactile feedback to the surgeon to assure sufficient tightening of the screws while avoiding stripping and are less prone to failure by breakage or by

loosening.

Another object of the invention is to provide bone screws which achieve optimal purchase within the bone, without the need to penetrate the posterior cortex of the vertebrae.

A further object of the invention is to provide plates which are textured or otherwise treated to promote bone growth from vertebrae to vertebra beneath the plate.

Another object of the invention is to provide a plate which is constructed to reliably engage an instrument for forming all bone screw holes coaxial with the holes formed in the plate, the instrument having integral depth limiting means which completely eliminates the danger of perforation of the posterior vertebral wall or entry into the spinal canal.

Yet another object of the invention is to provide a system in which the bone screws and locking mechanisms, when fully installed, have a low profile.

It is another object of the present invention to provide for an anterior cervical plating system which is at least in part bioresorbable.

It is another object of the present invention to provide for an anterior cervical plating system comprising at least in part of bone ingrowth materials and surfaces.

It is another object of the present invention to provide for an anterior cervical plating system comprising at

least in part of bone growth promoting substances.

It is another object of the present invention to provide instruments for reliably and easily performing the installation of the plates of the present invention.

It is still another object of the present invention to provide an improved method of installing the plates of the present invention.

The above and other objects and features of the invention will become more readily apparent from the following description of preferred embodiments of the invention, provided with reference to the accompanying drawings, which illustrate embodiments of the invention solely by way of non-limiting example.

SUMMARY OF THE INVENTION

The plating system of the first preferred embodiment of the present invention comprises a plate having a length sufficient to span a disc space and to overlap, at least in part, at least two adjacent cervical vertebrae, a substantial portion of the lower surface of the plate preferably being bi-concave, that is concave curved along a substantial portion of the longitudinal axis of the plate and concave curved along a substantial portion of the transverse axis of the plate. The lower surface of the plate may also textured and/or treated to

induce bone growth along the lower surface of the plate which contacts the cervical vertebrae. The plate is provided with a plurality of bone screw receiving holes which extend through the plate, from the upper surface to the lower surface of the plate, and at least one locking element is associated with the bone screw receiving hole. The plate and its component parts, may be made of any implant quality material suitable for use in the human body, and the plate and associated component may be made of a bioresorbable material.

Bone screws are each insertable into a respective bone screw receiving hole for attaching the plate to a vertebra. A locking element, is engageable to a locking element receiving recess and has a head formed to lock the bone screws to the plate. In the preferred embodiment, a single locking element locks a number of different bone screws in place. The locking elements are pre-installed prior to use by the surgeon in a manner so as to not impede installation of the bone screws.

As a result, the problems previously associated with the locking screws of the type applied after the insertion of the bone screws, including the problems of instrumentation to position and deliver to the plate the locking means, backing out, breakage, stripping and misthreading associated with the prior art more delicate locking screws resembling "watchmaker's parts", are eliminated.

In an alternative embodiment of the present invention, a locking element fits within a respective bone screw receiving hole to lock a respective one of the bone screws in place. According to this second embodiment of the invention, each of the bone screws is locked to the plate by means of an individual locking element which bears against at least a portion of the bone screw. Since no other holes need be formed in the plate to attach the locks to the plate, the plate remains quite strong.

The locking elements can be in many forms to achieve their intended purpose, such as, but not limited to, screws, threaded caps, rivets, set screws, projecting elements, and the like.

Also, a novel bone screw is disclosed so as to prevent pulling out of the bone screw during use. This is achieved by a design which includes a screw in which the outer diameter or crest diameter of the thread is maintained substantially constant along the entire length of the shaft of the bone screw, from below the head to above the tip, where threads of a lesser outer diameter facilitate insertion. The screw tip is fluted at its distal end to be self-tapping. The thread also has an extremely thin and sharp profile to cut into and preserve the integrity of the vertebral bone stock.

The plating system does not require that the head of the bone screw be hollow, or that additional holes be placed

through the plate in addition to those provided for the passage of the bone screws. It will be appreciated that bone screws are weakened when their heads are hollow and that plates are weakened when they are provided with additional holes.

Additionally, the plate of the disclosed systems permit the proper aligning of the holes in the plate for the bone screws and for the plate to be easily applied to the vertebrae in compression. The plates include appropriate slots and engagement means for engaging compression instrumentation, described in detail below, for applying a compression force between adjacent vertebrae to which the plate is attached, in a reliable and easy manner.

An improved locking screw driver is provided. The driver provides for a wedged interference fit with a recess in the head of the bone screws and the head of the locking elements. The same driver is usable for both bone screws and locking elements. The driver ensures that the locking element cannot fall off the driver and become lost in the wound. The driver has a tapered end to facilitate insertion into the complimentary recess in the head of the screws and is used to engage and pick up the locking elements. Alternatively, the receiving socket can be tapered to the same purpose.

Alternatively, a combination bone screw and locking screw driver is disclosed in which the bone screw driver passes

through a longitudinal opening in the locking screw driver so that both the bone screw and the locking screw can be loaded prior to insertion of the bone screw and both can be tightened with one instrument, without removing it from position.

Also, instruments are provided for forming pilot holes to assist in the ease and accuracy of the installment of the bone screws, and for creating a creating a compression force between adjacent vertebrae during installation of the plate and for holding the plate during installation.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 is a top perspective view of a first embodiment of a cervical spine multiple locking plate.

FIG. 2 is a top plan view of the cervical spine multiple locking plate shown in FIG. 1.

FIG. 3 is a side elevational view of the cervical spine multiple locking plate shown in FIG. 1.

FIG. 4 is an end view of the cervical spine multiple locking plate shown in FIG. 1.

FIG. 5 is a bottom plan view of the cervical spine multiple locking plate shown in FIG. 1.

FIG. 6 is a top plan view of the cervical spine multiple locking plate shown in FIGS. 1-5, with locking elements installed in an open configuration.

FIG. 7 is a top plan view of a modification of the plate of FIGS. 1-6 with a four bone screw locking element in place.

FIG. 8 is a top plan view of a further embodiment of a cervical locking plate of FIG. 1 with an elongated central slot for increased compression capability.

FIG. 9 is a top plan view of a locking element for use with the plates of FIGS. 1-6.

FIG. 10 is a top plan view of a locking element for use with the central opening of the plate of FIGS. 7 and 22.

FIG. 11 is a top plan view of a locking cap for use in the end openings shown in FIGS. 1, 6, and 7.

FIG. 12 is a side elevational view of the locking element of FIG. 16.

FIG. 13 is a side elevational view of another embodiment of the locking element of FIG. 16.

FIG. 14 is a top perspective view of an alternative embodiment of cervical spine multiple locking plate for use with locking rivets.

FIG. 15 is a bottom plan view of the cervical spine multiple locking plate of FIG. 14.

FIG. 16 is a top plan view of a two bone screw locking element.

FIG. 17 is a top plan view of an alternative embodiment

of a four bone screw locking element having head slits for increased flexibility of the locking tabs.

FIG. 18 is a bottom plan view of a rivet type locking element for use with the central opening of the plate of FIG. 14.

FIG. 19 is a side elevational view of a rivet locking element.

FIG. 20 is a top perspective view of the bottom portion of the head of rivet of FIG. 19 viewed along lines 20-20.

FIG. 21 is a top perspective view of the head portion of a three bone screw locking element.

FIG. 22 is a top perspective view of a third embodiment of a cervical spine multiple locking plate utilizing locking elements in the form of threaded caps.

FIG. 23 is a side elevational view of a locking element for use with the plate of FIG. 22.

FIG. 24A is a side elevational view of a bone screw in accordance with the present invention.

FIG. 24B is an enlarged side elevational view of the bone screw of FIG. 24A.

FIG. 25 is a side elevational view of an alternative embodiment of a bone screw in accordance with the present invention.

FIG. 26 is a bottom end view of the bone screw shown in FIG. 24A.

FIG. 27 is a top end view of the bone screw shown in FIG. 24A.

FIG. 28 is a top perspective view of a fourth embodiment of a cervical spine multiple locking plate.

FIG. 29 is a top perspective view of a locking element for use with the plate of FIG. 28.

FIG. 30 is a partial side sectional view of the plate of FIG. 28 along lines 30-30 with a bone screw in place.

FIG. 31 is a top perspective view of the plate of FIG. 1 positioned against the anterior aspect of three successive vertebral bodies in the cervical spine, a plate holder, and an instrument for forming bone screw receiving holes in to the vertebral bodies.

FIG. 32 is a cross-sectional view of a portion of the bone forming device shown in FIG. 31 viewed along lines 32-32.

FIG. 33 is a side elevational view in partial cross section illustrating a compression post tool and a compression post engaged to it for insertion into a vertebral body.

FIG. 34 is a side elevational view in partial cross section of the compression post tool engaged for removal of the compression post from the vertebral body.

FIG. 35 is a bottom end view of the compression post tool of FIG. 34.

FIG. 36 is a side elevational view of a plate engaging

hook for use with the compression apparatus shown in FIG. 38.

FIG. 37 is a cross-sectional view through the plate of an alternative embodiment of a hole forming instrument in the form of a drill guide and drill for use during the plate installation procedure.

Fig 38 is a side elevational view showing intersegmental compression of the spine and compression apparatus.

FIG. 39 is a view similar to that of FIG. 38 showing the compression apparatus in a further stage of the plate installation procedure.

FIG. 40 is a top perspective view showing the locking of the bone screws to the plate.

FIG. 41 is a partial side sectional view of a locking element attached to a driver instrument.

FIG. 42 is a partial side sectional view of another embodiment of the locking element attached to a driver instrument.

FIG. 43 is a partial cross-sectional view showing a cervical plate, locking element, and bone screws along lines 43-43 of FIG. 40.

FIG. 44 is an enlarged portion of detail along line 44 of FIG. 43.

FIG. 45 is a side view in partial cross section of a

plate holder attached to a plate.

FIG. 46 is a side view in partial cross section of another embodiment of a plate holder attached to a plate.

FIG. 47 is a top perspective view of a first embodiment of a single locking plate.

FIG. 48 is a top plan view of the plate shown in FIG. 47.

FIG. 49 is a side elevational view of the plate shown in FIG. 47.

FIG. 50 is an end view of the plate shown in FIG. 47.

FIG. 51 is a bottom plan view of the plate shown in FIG. 47.

FIG. 52 is a top plan view of the plate shown in FIG. 47, with locking elements in place.

FIG. 53 is a side elevational view of a bone screw used with the plate shown in FIG. 47.

FIG. 54 is a top end view of the bone screw shown in FIG. 53.

FIG. 55 is a bottom end view of the bone screw of FIG. 53.

FIG. 56 is a top plan view of a locking cap for use with the single locking plate of FIG. 47.

FIG. 57 is a side elevational view of the locking cap shown in FIG. 56.

FIG. 58 is a bottom plan view of the locking cap shown in FIGS. 56 and 57.

FIG. 59 is a bottom perspective view of the locking cap of FIGS. 56-58.

FIG. 60 is a top perspective view of the single locking plate of FIG. 47 shown being held by a plate holder against three vertebral bodies, with the hole forming instrument for punching a pilot hole into the vertebral bodies for receiving a bone screw.

FIG. 61 is a side elevational view in partial cutaway of the hole forming instrument threaded to a bone screw receiving hole.

FIG. 62 is a perspective side sectional view of the drill and drill guide threadably engaged to the plate for drilling a hole for insertion of a bone screw.

FIG. 63 is a top perspective view of a single locking plate installed along a segment of the spine with two locking caps installed in two bone screw receiving holes.

FIG. 64 is a side elevational view in partial cross section of a locking cap engaged to a driver for installing the locking cap.

FIG. 65 is a partial cross sectional view of the plate, bone screws and locking caps along line 65--65 of FIG. 63.

FIG. 66 is an enlarged fragmentary view of area 66 of FIG. 65.

FIG. 67 is a perspective view of a cervical locking plate being held by an alternative plate holder instrument.

FIG. 68 is an end sectional view showing the plate holder of FIG. 67 engaging a plate.

FIG. 69A is an end sectional view of an alternative embodiment of the plate holder.

FIG. 69B is an end sectional view of another alternative embodiment of the plate holder.

FIG. 70 is a plate holder instrument with an offset and removable handle.

FIG. 71 is a top perspective view of a second embodiment of a cervical single locking plate having individual locking elements to lock each bone screw.

FIG. 72 is a top perspective view of a threaded locking element for use with the cervical single locking plate of FIG. 71

FIG. 73 is a partial side sectional view of the plate of FIG. 71 viewed along lines 73-73 with the locking element of FIG. 72 in place to hold a bone screw, but not fully tightened.

FIG. 74 is a top perspective view of an alternative locking element for use with a first modification of the cervical single locking plate of FIG. 71.

FIG. 75 is a side sectional view of the first modification of the plate of FIG. 71 with the locking element of FIG. 74.

FIG. 76 is a perspective view of an alternative locking element for use with the first modification of the plate of FIG. 71.

FIG. 77 is a partial side sectional view of the first modification of the plate of FIG. 71 with the locking element of FIG. 76 in place.

FIG. 78 is a top perspective view of another alternative locking element in the form of a rivet for use with a second modification of the locking plate of FIG. 71.

FIG. 79 is a partial side sectional detail view of the plate of FIG. 71 modified to use a locking element of FIG. 78 shown in place.

FIG. 80 is a partial cross sectional view of a plate and bone screw with the end of a tool shown for use in inserting both the bone screws and locking caps.

FIG. 81 is a side elevational view of another embodiment of the tool of FIG. 80.

FIG. 83 is a further embodiment of a cervical spine multiple locking plate for use in stabilizing multiple segments of the spine.

FIG. 84A-84E are various embodiments of cervical spine multiple locking plates for use in stabilizing a single segment of the spine.

DETAILED DESCRIPTION OF THE DRAWINGS

The present invention will be described first in association with the preferred embodiment of the plate system in which a plurality of bone screws are locked in place with one locking element. This is referred to as the multiple locking plate system. The multiple locking plates will be described, then the locking elements for locking the bone screws to the plate, then the bone screws associated with the multiple locking plates, and finally the instrumentation and method of installation of the multiple locking plates. Thereafter the plate systems in which a single locking element locks a single bone screw will be described. This is referred to as the single locking plate system. The locking elements, bone screws, instrumentation, and method of installation associated with the single locking plate will then be discussed.

1. Multiple Locking Plate System

The preferred embodiment of the multiple locking anterior cervical locking plate 2 according to the present invention (here shown by way of example for use in a two level fusion (three adjacent vertebrae)) is shown in FIGS. 1-5. Plate 2 has a generally elongated form whose outline generally departs from rectangular due to the presence of lobes or lateral projections 4 at the corners and at the center of the sides of

plate 2. Each lobe 4 has a rounded outline and contains a respective circular bone screw receiving hole 6. Two additional intermediate circular bone screw receiving holes 8 are located inwardly of the sides of plate 2 and are centered on the longitudinal center line of plate 2. Lobes 4 give plate 2 additional strength in the region surrounding each bone screw receiving hole 6. It is recognized that other shapes for the plate 2 may be employed.

The intermediate paired bone screw receiving holes 8 are for use with a two level (three vertebrae) fusion. The intermediate bone screw receiving holes 8 may be eliminated for a single level (two vertebrae) fusion, or additional intermediate bone screw receiving holes 8 may be added if additional levels are to be fused.

Plate 2 is further provided with three locking element holes 12, each of which in the preferred embodiment is internally threaded 3, and each of which is surrounded by a shallow countersunk region 14. As will be described in greater detail below, in the preferred embodiment, bone screws are inserted in the bone screw receiving holes and a single pre-installed locking element associated with each of the locking element holes 12 locks a number of bone screws 30 in position at one time.

The number of paired bone screw holes generally

correspond to the number of vertebrae to be fused. A plate for a one level fusion could have but a single locking element hole 12, while plates for fusing more than two levels (three vertebrae) could have additional middle locking element holes 12 corresponding to additional paired bone screw holes. In the embodiment illustrated in FIGS. 1-6, each end locking element 20 will lock three bone screws 30 in place, while the locking screw 21 in the central locking hole 12 locks two bone screws 30 in place. As shown in FIG. 7, central locking element 25 can also be configured so that four bone screws 30 are locked at one time.

As shown particularly in FIGS. 3, 4 and 5, plate 2 is shaped so that its bottom surface 27 (the surface which will be in contact with the vertebral bodies) has a bi-concave curvature, being concave both in the longitudinal plane (corresponding to its length) and in the plane transverse thereto, corresponding to its width. The concave curvature in the longitudinal plane conforms to the proper shape of the anterior aspect of the spine with the vertebrae aligned in appropriate lordosis. That longitudinal curve is an arc along the circumference of a circle (referred to herein as the "radius of curvature") 15.0 cm to 30.0 cm in radius and more preferably 20.0-25.0 cm in radius. Viewed on end in FIG. 4, the plate 2 has a radius of curvature of a circle 15-25 mm in radius, but preferably 19-21 mm in radius. While the plate 2 may have a thickness between 2 to 3 mm, a

thickness of between 2.25 and 2.5 mm is preferred.

Having the bottom surface 27 of plate 2 contoured so that it is able to lie flush against the associated vertebral bodies is in contrast to conventional plates which have larger radii of curvature that contact the vertebral bodies only along the longitudinal centerline of the plate, thereby permitting side-to-side rocking of the plate relative to the vertebral bodies. The contour of the plate of the present invention provides effective resistance to rocking of the plate 2 relative to the vertebral bodies about the longitudinal center line of the plate, thereby reducing stress on the plate 2 and bone screws 30, and preventing the soft tissues from becoming engaged beneath the plate.

Other advantages produced by the above curvature are that the plate 2 will conform more closely to the facing bone surface; the plate 2 will project from the spine by a smaller distance; soft tissue will be prevented from sliding underneath the edges of the plate 2, where it could be subject to damage; and the angle of the bone screws 30, perpendicular to the plate when viewed from the side, when installed will be at a substantial converging angle, trapping the vertebral bone between the bone screws 30, and thus more strongly anchoring the plate to the spine.

As shown in FIG. 5, the bottom surface 27 of plate 2,

preferably has a porous, roughened, and/or textured surface layer and may be coated with, impregnated with, or comprise of fusion promoting substances (such as bone morphogenetic proteins) so as to encourage the growth of bone along the underside of the plate 2 from vertebrae to vertebrae. The textured bottom surface 27 also provides a medium for retaining fusion promoting substances with which the bottom surface 27 layer can be impregnated prior to installation. The bottom surface 27 of plate 2 may be given the desired porous textured form by rough blasting or any other conventional technology, such as etching, plasma spraying, sintering, and casting for example. If porous, the bottom surface 27 is formed to have a porosity or pore size in the order of 50-500 microns, and preferably 100-300 microns. Fusion promoting substances with which the porous, textured bottom surface 27 can be impregnated include, but are not limited to, bone morphogenetic proteins, hydroxyapatite, or hydroxyapatite tricalcium phosphate. The plate 2 may comprise of at least in part a resorbable material which can further be impregnated with the bone growth material so that as the plate 2 is resorbed by the body of the patient, the bone growth material is released, thus acting as a time release mechanism. Having the plate 2 being made from a material that is resorbable and having bone growth promoting material present permits the vertebrae to be fused in a more natural manner as the plate becomes progressively

less load bearing thereby avoiding late stress shielding of the spine.

As further shown in FIGS. 4 and 5, at least one end of plate 2 has a recess 18 that can cooperate with a compression apparatus, described in detail later in reference to FIGS. 36 and 38.

FIG. 6 is a top plan view of the plate 2 of FIG. 1 with locking elements 20, 21 inserted into the locking element receiving holes. In the preferred embodiment, the locking elements 20, 21 are in the form of screws that cooperate with the threaded interior 3 of the locking holes 12. Each of these locking elements 20, 21 is shown in its initial open orientation, where the orientation of the cutouts 22 in the head 23 of each locking element 20, 21 is oriented so as to permit introduction of bone screws 30 into adjacent bone screw receiving holes 6,8 without interference by the head 23 of the locking element 20, 21. It is appreciated that other configurations of the head 23 are possible so as to permit introduction of bone screw into adjacent bone screw receiving holes without interference by the head 23.

FIG. 8 is a top view of another embodiment of plate 2 of FIGS. 1-5, and is generally referred to as plate 120. Plate 120 is provided with a longitudinally extending elongated slot 122 along its longitudinal axis which is superimposed on the

middle locking hole 12. Elongated slot 122 allows additional relative movement between plate 120 and a compression post 54 associated with a compression tool during the compression procedure, as discussed below.

Referring to FIGS. 14 and 15, an alternative embodiment of a multiple locking plate referred to by the number 70 is shown. In plate 70, rather than the threaded locking hole 12, a central opening 200 for receiving a removable rivet 202, of the type shown in FIGS. 17-20, is provided. FIG. 15 is a bottom plan view of the plate 70 shown in FIG. 14. The contour of the plate 70 is the same as that of the plate 2 shown in FIGS. 1-5. The rivet 202 is removable and fits within the unthreaded opening 200, comparable to the locking hole 12 and slot 122 described above. Other embodiments may employ a rivet that is not removable, but is manufactured as part of the plate 70 as would be used in the end locking holes 19 of FIGS. 14 and 15.

Referring to FIG. 22, another alternative embodiment of a multiple locking plate is shown and is generally referred to by the number 230. The plate 230 uses threaded caps, such as cap 300 shown in FIGS. 9 and 23, for a locking element or preferably one with cut outs as described having an appearance in a top view such as the locking element in FIGS. 10-11, for example. The central locking hole 602 has an elongated slot 234 for providing an increased compression capability, as will be discussed further

herein.

Referring to FIGS. 10-13, a first embodiment of a locking element 20, 21, 25 in the form of locking screws according to the present invention for use with plate 2 is shown. FIG. 10 is a top plan view which illustrates the head 23 of the central locking element 25 shown in FIG. 7. The shaft 46 of locking element 25 is threaded 47 to mate with the threading 3 within the associated locking hole 12 of plate 2. As shown in FIG. 21, each segment 49 on each side of cutouts 22 of the locking element 21 has a bearing surface 48 formed at the lower surface of locking element head 23. As shown in Fig 16, the locking element head 23 can be provided with two slots 42 for providing flexibility to the locking element head 23 to assist in the locking element's ability to ride over the top of the bone screw head 32 during the bearing action when the locking element is rotated. Alternatively, it is appreciated that the bearing surface can be cammed, ramped or wedged. The cammed, ramped or wedged features can also be used with the other locking elements described herein.

Referring to FIGS. 6 and 10-13, it will be appreciated that when the locking elements 20, 21 are rotated in the clockwise direction with respect to the view of FIG. 6, a respective bearing surface 48 will ride upon the curved top surface 39 of a respective bone screw head 32 in order to

positively lock the associated bone screws 30 and the locking elements 20, 21 in place.

Alternatively, as shown in FIG. 21 in place of a bearing surface 44, a ramp or wedge shaped surface 44 may be used to increase the force applied to the bone screw head 32. When locked, the leading end of the ramped portion of the locking element would be lower than the prominence of the bone screw head 32 so that more force is needed to lift the locking element and untighten it than is needed for the locking element to remain tight and locked. However, the locking element heads 23 need not have slots, be cammed, or have a ramped surface to achieve the locking of the bone screw 30 in place. Pressure, friction, interference fits, or other engagement means capable of preventing the locking element from moving from its locked position may be employed.

The rivet 202, shown in FIGS. 17-20 is intended for use in association with plate 70 shown in FIGS. 14-15, is shown in detail in cross section in FIGS. 19 and 20. The rivet 202 has a head 204, a shaft 206, and an elongated bottom segment 208 for fitting within the corresponding opening 200 in the plate 70. The lower surface 210 of the head 204 of the rivet 202 has an irregular surface which may be cammed, such as on the bottom of locking element 20, 21, for engaging the top surface 39 of the bone screw head 32. For use in the end locking holes 19, the

upper surface of the elongated bottom segment 208 can have an irregular surface for cooperating with the irregular surface of the bottom of the plate 70 to hold the rivet 202 in the locked position against the bone screw head 32, as shown in FIG. 15. While the rivet of FIG. 18 is a separate, removable component from the plate, the rivets, and particularly those for use with the end locking holes, can be formed as part of the plate during the manufacturing process of the plate and rivet can be non removable.

Each of the above embodiments provides tight attachment of the locking element relative the bone screw 30 and relevant plate.

In the alternative embodiment of multiple locking plate 23 shown in FIG. 22, the locking element can be in the form of threaded locking cap 300 shown in FIG. 23. The threaded locking cap 300 has a thread 302 on its outer circumference corresponding to the thread 303 on the inner circumference of the locking element depressions 304 in the top of the plate 230 shown in FIG. 22. The locking cap 300 is relatively thin, particularly compared to its width. The top 305 of locking cap 300 is provided with a noncircular through hole 306 for receiving a similarly configured driving tool.

Referring to FIGS. 28, 29, and 30 another embodiment of the multiple locking plate generally referred to by the number

002720" 8958F860

400 and a locking element in the form of a thin locking member 412 are shown. Plate 400 has an opening in its top surface for insertion of the thin locking member 412, a recess 402 associated with each of the bone screw receiving holes 408 and a slot 410 in the side wall of the bone screw receiving holes 408 to permit the thin locking member 412, having a series of thin projections or blades 414, thinner than the slot 410, that give this locking member 412 an appearance similar to that of a propeller. The thin locking member 412 is able to be rotated within the plate so as to not cover the bone screw holes, thus allowing the thin locking member 412 to be pre-installed prior to the installation of the bone screws by the surgeon. Limited rotation of the thin locking member 412 allows the blades 414 to protrude through the slot 410 and to cover a portion of the top of the associated bone screws 30. The blades 414 of the thin locking member 412 are flexible and, when rotated, slide over the top surface 39 of the bone screw head 32 to lock the bone screw 30 in place. As with the other embodiments discussed, each of the embodiments of the locking element is capable of locking more than one bone screw 30. It is appreciated that the various multiple locking plates and locking element combinations are capable of locking as many as four bone screws at once, but are equally effective for locking a lesser number or none at all, that is securing itself to the plate.

It will be noted that one characteristic of each of the above described locking element embodiments is to have a driver engagement means, in these cases for example, a recess 24 as large as the recess 34 in the bone screws 30 so that the same tool can be used to turn both the bone screws 30 and the locking elements. Also, the locking elements are sufficiently strong and have sufficient mass so as to be able to withstand being locked without breakage.

All of the shown examples of the multiple locking elements that have a number of cutout portions have an arc with a radius greater than that of the bone screw head. In addition, the head 23 of each locking element 20, 21 is provided at its center with a noncircular recess 24, such as shown in FIG. 9 which is engageable by an appropriate manipulation tool, such as shown in FIGS. 40-42. In the embodiment of head 23 shown in FIG. 9, the associated tool would have a hex head, but as discussed with regard to FIGS. 80 and 81, other shapes of recesses in the head 23 may be used. The thread of each locking hole 12 and of each locking element 20, 21 has a close tolerance so that they will reliably retain their orientations so as to permit introduction of bone screws 30 into bone screw receiving holes 6, 8 without interference.

It is appreciated that while various forms of locking elements have been disclosed, in light of the teaching, other

equivalent means can be used for the purpose of locking the bone screws 30 in place. In FIG. 83, an alternative multiple locking plate 990 is shown having additional intermediate bone screw receiving holes 980 and associated locking elements 960 for locking bone screws 30 in place. Plate 990 allows for a more close spacing and more pairs of bone screw holes than the number of vertebrae to be engaged.

In FIGS. 84A-84E various plates 700a-g used for a single level fusion are shown. Each of these plates 700a-g is designed to span one spinal segment consisting of one disc space and two adjacent vertebrae (containing the bone graft), and have bone screws inserted into the end of the vertebrae through the bone screw receiving holes 6 associated with the two adjacent vertebrae and then locked in place. As shown in Figures 84A-84E, one locking element 710, or two locking elements can be used to lock four bone screws in place. In FIGS. 84A-84E, each of the plates 700a-e is shown with the locking elements in their open orientation, before being rotated to lock the bone screws.

Each of the above described plates can have the same generally biconcave contour as already described for conforming to the anterior aspect of the spine.

FIGS. 24A and 24B provide a side view of one embodiment of a bone screw 30 according to the present invention. FIG. 27 is a top view of the bone screw 30. At the center of bone screw

head 32 is a profiled recess 34 which may have the same form as the recess 24 of each locking element 20, 21 in which case it may be turned with the same tool as that employed for turning locking elements 20, 21. It is appreciated that the driver engaging portion of the bone screw 30 could be slotted, and be either male or female (as is shown).

In the embodiment of bone screw 30 shown in FIGS. 24A and 24B, the bone screw head 32 is stepped, with the first lower head portion 35 being contiguous with the screw shank 33 and has a smaller diameter than the upper portion of the bone screw head 32. When this embodiment of bone screw 30 is employed, each bone screw receiving hole 6, 8 of the plate 2 has a countersunk region 14 matching the diameter of the upper portion of the bone screw head 32 and dimensioned for an interference fit. The lower portion 35 of the bone screw head 32 is dimensioned to achieve an interference fit with its associated portion of bone screw receiving holes 6, 8. The larger diameter upper portion of bone screw head 32 assures that the bone screw 30 cannot be advanced completely through bone screw receiving holes 6, 8 of plate 2. The bone screw 30 passes completely through the upper surface of the plate 2 without engaging the upper surface in any way.

As shown in FIG. 44, the head 32 of screw 30 passes unobstructed through the upper surface of the plate until the lower surface of enlarged screw head 32 engages the upper face of

interference fit in the associated bone screw receiving hole 6,8 when the bone screw 30' has been fully installed. When this embodiment of bone screw 30' is employed, bone screw receiving holes 6, 8 need not be provided with a countersunk region 4.

In each of the above embodiments of the bone screws, the bone screws 30 and 30' present a unique combination of a tapered screw shaft 33 and a helical thread 31. The diameter of screw shaft 33 generally increases from a distal portion of the shaft near the screw tip 36 toward the proximal portion of the shaft near screw head 32. In the preferred embodiment, the rate of increase in diameter is also greater near the bone screw head 32. Such a shape avoids stress risers and provides increased strength at the screw-plate junction, where it is needed the most. The tapering of screw shaft 33 may have a concave form, as shown in FIG. 24A, or may be linear. The distal portion of the screw shaft 33 may assume a constant diameter.

Referring again to FIGS. 24A and 24B, the thread 31 of the bone screw 30 has a substantially constant outer, or crest, diameter "d" from the proximal portion of the shaft below the bone screw head 32 to the distal portion of the shaft near the bone screw tip 36. In the screw tip 36, the crest diameter of thread 31 may be reduced for preferably one to two turns to facilitate the insertion and penetration of the bone screw 30 into the bone.

In the preferred embodiment, the thread 31 of each bone screw 30 has an outer diameter slightly smaller than the diameter of the lowest portion 35 of the bone screw head 32, which is adjacent the trailing, or upper, end of the associated thread 31. In addition, the thread 31 is relatively thin, in the direction of the longitudinal axis of the screw, and tapers outwardly, and has a cross section of a triangle.

An example of the dimensions of a bone screw for use in human anterior cervical spinal surgery for insertion into the vertebrae is as follows: the threaded portion of said screw has a length from about 10 mm to about 22 mm (12 - 18 mm preferred) and a head length from about 1 mm to about 3 mm (2 - 2.5 mm preferred). The threaded portion should have a maximum outside diameter from about 3.6 mm to about 5.2 mm (3.8 - 4.5 mm preferred) and the head has a diameter from about 3.8 mm to about 6 mm (4 - 5.5 mm preferred). The thread pitch is from about 1.25 mm to about 2.5 mm (1.5 - 2.0 mm preferred) and has a sharp and thin threaded profile. The apex of the two faces of the thread have an angle of less than about 21 degrees (15 degrees preferred) and the base of the thread is less than about 0.60 mm thick (0.25 mm - 0.35 mm preferred). The screw has a root diameter that increases from proximately above the tip of the shank, along the longitudinal axis to proximately below the head portion of the screw. Preferably, the tip of the screw tip is

fluted by at least one cut out section so as to make the screw self-tapping.

Even though the thread 31 of the bone screw 30 has a thin profile, the thread will nevertheless be stronger than the bone into which it is introduced so that this thread will efficiently cut a thin helical groove in the bone tissue. The volume of bone that will be displaced by the thickness of the thread is minimized by the thin form of the thread, yet the substantial crest diameter of the screw thread maximizes the surface area of the threads in contact with the bone. While enlarging the screw shaft 33 diameter near the bone screw head 32 increases its strength where needed, reducing the screw shaft 33 diameter away from the bone screw head 32 where such strength is not required allows for the maximum area of engagement for the thread 31 to the bone.

In the preferred embodiment, as shown in FIGS. 24A and 26, bone screw tip 36 is provided with cutting flutes 38, to make the bone screw 30 self-tapping. Unlike the prior art bone screws, used for anterior cervical spinal surgery which are not self-tapping, the thread form of the present invention screw is itself more like a tap than a conventional screw in that the threads are very sharp and fluted. Additional embodiments of the bone screws 30 is shown in FIGS. 53-55.

By way of example, plates for fusing three adjacent

vertebrae (2 interspaces, or two spinal segments) are shown. Each set of the bone screw receiving holes associated with a vertebrae is considered to be a segment of the plate so that for example, in FIG. 1 three segments are shown-- an upper, a central, and a lower segment. While the present discussion is in association with plates for use in fusing three vertebrae across two interspaces, it should be understood that longer and shorter plates having the appropriate number and location of bone screw receiving holes corresponding to the number of vertebrae to be fused are contemplated, and would take the form of the plates shown with fewer or more intermediate segments, such as the segment along line 9 of FIG. 1, or the intermediate segments of the plates shown in FIGS. 82-84F.

Referring to Figures 31-42, an outline of the steps of the method for installing the plates of the present invention is set forth below. A detailed description of the instrumentation and method for installing the plates of the present invention follows the outline.

Step 1

Having completed the interbody fusions, the surgeon removes any bone spurs or localized irregularities along the front of the spine of the area to be fused.

Step 2

The correct length plate is selected by the surgeon by

measuring the distance on the spine by a caliper, ruler, template, and the like. That plate having a length sufficient to span the distance of the spine to be fused and to partially overlap a portion of each of the end vertebrae to be fused.

Step 3

Utilizing a plate holder, the plate is placed into the wound and positioned to confirm positioning, length, and screw hole alignment relative to the segments of the spine to be fused.

Step 4

As shown in FIG. 31, with the plate thus positioned and securely held, the plate may be attached to any of the vertebrae to be fused (by example only, here shown as the top vertebra).

Sub-Step 4A

The pilot (guide) hole punch 60 is attached to the plate 2 as per FIG. 32, or alternatively, while not preferred the drill guide may be used as per FIG. 37. In either event, the pilot hole forming means rigidly aligns with and is captured by the plate bone screw receiving hole wall.

Sub-Step 4B

The pilot hole is then formed by impacting the pilot hole punch of FIG. 32 or drilling with the drill of FIG. 37. In the alternative while not preferred, the formation of the pilot hole can be done away with altogether and the correct screw selected so as to have a length less than the distance along its

path to the posterior vertebral cortex can be directly inserted.

The determination of the appropriate screw length is made by measuring or templating from radiographs, MRI's, or CT scans, or determined directly by measuring the depth of the disc space.

Step 5

The correct screw is then attached to the screw driver which regardless of the specific form of the screw driver engagement means, is designed to have an interference fit so as to remain firmly bound to the driver during transport to the insertion site. FIGS. 41, 42, 63, 64, 80 and 81 show various ways of achieving such a fit of the driver and screw. In addition to a wedging at the screw and driver interface, clips, and springs and other means are well known for temporarily and reversibly securing the screw to the driver, such as is shown in FIG. 80 where a slotted inwardly springing sleeve holds a threaded cap peripherally until, as it is screwed into the plate, it is automatically pushed back releasing the threaded cap.

Once a first bone screw has been fully inserted into a vertebra through the plate, it is preferable to insert the other of the transverse pair in the manner already described as per FIG. 33.

In a similar manner, it is possible to insert the remaining bone screws as per the surgeon's preference into each

of the vertebrae to be included into the fusion, just the end vertebrae of the fusion construct, or additionally place screws into the fusion grafts.

However, as shown in FIGS. 33, 34, 38 and 39, it is possible with the present invention at the surgeon's option to place any portion or all of the fusion construct under compression and to do so intersegmentally or across the entire length of the fusion construct even when multi-segmented.

It is appreciated that the same procedure could be generally used for any of the plate systems of the present invention.

As shown in FIG. 31, the vertebrae 50a-c are separated from one another by fusion graft blocks 51 which were previously installed in the spinal disc space between adjacent vertebrae 50 forming a fusion bone graft construct. Plate 2 is shown in FIG. 31 with the locking elements 20, 21 removed in order to simplify the illustration. It will be understood, however, that in the preferred embodiment the locking elements 20, 21 can be, and preferably are, pre-installed in the positions shown in FIG. 6 prior to positioning plate 2 upon vertebral bodies of the vertebrae 50, thereby saving the surgeon time and trouble.

Plate 2 may be held in position by any known plate holding means, but preferably by the holding tools shown in FIGS. 45, 46 or 70 by the notches 142 in the sides of the compression

arms 104, 130 of a vertebral compressor tool 100 shown in FIG. 39, or as a further alternative, by the unitary plate holder similar to the FIG. 70 design.

As shown in FIG. 45, plate holder 870 has a hollow tubular housing 872, with a central rod 874 having a thread 878 at one end for engaging one of the threaded locking holes 12 in the plate 2. The bottom end of the housing 872 has projections 880, 882 that extend outwardly and then downwardly to fit into the bone screw receiving holes 8 of the plate 2 preventing the housing 872 from rotating. The central rod 874 is located in the housing 872 such that it can be rotated by rotating a handle (not shown) which is fixed to the central rod 874 at its upper end.

In FIG. 46 an alternative embodiment of the plate holder 890 is shown. A single solid member 890 has a threaded projection 894 at its bottom end for attachment to the central threaded locking hole 12 in the plate. The bottom surface of the holder 890 of this embodiment is contoured so as to match the contours of the top surface of the plate adjacent to the locking hole 12, shown as a depression 14.

Referring to FIGS. 67-68, an embodiment of a plate holder for holding any of the plates while being positioned on the vertebrae is shown and generally referred to by the number 800. The plate holder 800 has a hollow tubular housing 802, with a central rod 804 having a handle 806 at one end and a thread 808

at its other end for engaging one of the threaded locking holes 12 in the plate 600. The bottom end of the housing 802 has projections 810, 812 that extend outwardly and then downwardly 814, 816 to fit along the side edge of the plate 2 between the end and intermediate lobes 4, preventing the housing 802 from rotating. The central rod 804 is located in the housing 802 such that it can be rotated by rotating the handle 806 which is fixed to the central rod 804 at its upper end. This central rod 804 can also be attached to the housing 802 so that it can move up and down to some extent, by any number of conventional ways, such as by having the central rod 804 have an annular depression with a length of approximately 3-5 mm, and a set screw projecting inward from the housing to engage the central rod 804. Once the plate 600 is in the proper place and the plate is attached to one of the vertebrae by bone screws 30, the central rod 804 is disconnected from the opening in the plate 600 and the holder 800 is removed.

FIG. 69A is an alternative embodiment of the plate holder 850. A single solid member 852 has a threaded projection 854 at its bottom end for attachment to the central threaded locking hole 12 in the plate. The solid member 852 could also be threaded into a bone screw receiving hole 6. The bottom surface of the holder 850 of this embodiment is contoured so as to match the contours of the top surface of the plate adjacent to the

locking hole 12, shown as a depression 14.

FIG. 69B is another embodiment of the plate holder 850'. A housing 851' having an end 853' configured to engage a bone screw receiving hole 6 contains a rod 855' having an uneven diameter and having a threaded portion 857'. As rod 855' is rotated by a handle similar to handle 806 shown in FIG. 68, rod 855' screws downward into the housing 851' into matching threads 858'. As the end of rod 855' is driven down, it spreads portions 859a' and 859b' (859c' and 859d' not shown) wedging plate holder 850' into a bone screw receiving hole of the plate. Plate holder 850' is best used with non-threaded bone screw receiving holes, but works for all types of bone screw receiving holes.

Referring to FIG. 70, an alternative embodiment of the plate holder referred to by the number 800' is shown in which there is a removable handle 860 that is used for first attaching the plate holder 800' to the plate, by rotating the shaft 804, and then for holding the plate holder 800' off to the side by extension 864, during the attachment procedure reducing the interference of the plate holder 800 with the surgical procedure.

Referring to FIG. 38, a compression tool 100 is shown with a toothed gear bar 102 having a first compression arm 104 secured to its free end. Compression arm 104 has at its distal end a bore 106 for removably holding either a plate engaging element 108, shown in FIG. 36, having a hook 110 at one end for

engaging a depression or notch 18 in the end of plate 2, or for removably holding a compression post 54 shown in FIGS. 33-34. As shown in FIG. 36, plate engaging element 108 includes a shaft 112 that will be inserted into the corresponding bore 106 of compression arm 104, and a flange 115 for resting against the bottom face of bore 106 to accurately limit the depth of insertion of plate engaging element 108 into the bore 106. A ring spring 128, preferably of metal, is located in an annular depression of the shaft 112, for holding the plate engaging element 108 in the bore 106.

Referring to FIGS. 38-39, compression tool 100 includes a second moveable compression arm 130 movable along toothed bar 102 parallel to first compression arm 104. The distal end of the second compression arm 130 also has a bore 132, the same as bore 106, that can receive a removable post 134. Bores 106 and 132 are the same so that either compression arm 104, 130 can be used to hold the removable post 134, permitting the compression tool 100 to be used in any orientation. By permitting the plate engaging element 108 and the compression post 54 to both rotate and slide in the bores 106, 132 of the two compression arms 104, 130, with the plate engaging hook 110 able to work even at an angle to the plate allows for the apparatus to be readily attachable to the spine through the compression post 54 and plate.

Compression arm 130 has a driving assembly consisting of a toothed wheel (not visible) which is engaged with the tooth gear 138 of bar toothed gear 102 and is connected to compression arm 130 such that compression arm 130 is movable along the length of toothed gear bar 102 by means of the rotation of handle 140, which is connected to the toothed wheel. When the handle 140 is turned in the direction of the arrow shown in FIG. 38, compression arm 130 is moved toward compression arm 104. The driving assembly has a self lock release mechanism whereby the movement of the two compression arms 104, 130 away from one another is prevented, without the activation of the release. On the inward distal end of each compression arm, on facing sides, is a notch 142 or recess for holding the plate 2 along its sides between the central lobes 4 and end lobes 4, as shown in FIG. 37.

While the toothed gear bar 102 and compression arms 104, 130 have been described as being straight, it is possible that the toothed gear bar 102 and compression arms 104, 130 may be arcuately or otherwise shaped, so as to induce lordosis in the vertebrae, if so desired.

As shown in FIG. 31, in the event that the compression tool 100 is used to hold the plate 2, the ends 144 of the compression arms 104, 130 will be located in line with the fusion graft construct 51 which was placed in the disc space when plate 2 is properly positioned. A gap will exist between plate 2 and

each fusion graft construct 51, providing a space to accommodate the free ends of arms 104, 130 should they extend beyond the bottom surface of the plate 2. As will be described below, the same compression tool 100 can also be used for compressing a plurality of cervical vertebral bodies with bone grafts interposed during the attachment of plate 2 to the vertebrae 50.

Referring to FIG. 31, plate 2 is held by a suitable holder, in this case shown as the compression arms 104 and 130. Once the appropriate length plate 2 has been properly positioned so that the bone screw receiving holes 6 are aligned with each of the respective vertebrae 50a-c to be fused, the next step is the formation of bone screw receiving holes 6 prior to installation of the bone screws 30 themselves in the vertebrae 50a. While the procedure is described as first attaching the plate 2 to the upper vertebrae 50a, the plate 2 can be attached to any of the vertebrae in any order. Different sized plates are used so that, as indicated above, the physician will select the appropriate sized plate in which the bone screw receiving holes 6, 8 are aligned with the three adjacent vertebrae 50a, 50b and 50c. Pilot holes are formed by a pilot hole forming apparatus 60 shown in FIGS. 31 and 32. Unlike with known prior art and screw plating systems, the bone screws 30 may be inserted without the prior formation of an opening into the vertebrae as the bone screws 30 are preferably sharp pointed, self-tapping, and have at

their tip a diminishing major diameter to assist the screw entering and pulling into the bone. However, while a hole into the bone of the vertebrae may be formed prior to screw insertion, it is preferable that the hole be of a smaller diameter than the root diameter of the screw and for a different purpose than with the prior art. With the prior art the hole drilled had to be of a diameter equal to but preferably larger than the root (minor) diameter of the screw, as the screws were not self-tapping. It is desirous to create pilot holes to assure that a proper path for the bone screws 30 is maintained, and also to prevent damage to the vertebral bone during insertion of the bone screws 30. In addition, the pilot hole forming apparatus 60 creates a more compact vertebral bone mass for reception of the self-tapping bone screw 30 used in this insertion.

As shown in FIGS. 31 and 32, pilot hole forming apparatus 60 includes a hollow cylindrical housing 62 having a bottom provided with a through hole 63. Housing 62 contains a central shaft 64 which extends through the through hole 63 in the bottom of housing 62. The leading end 66 of shaft 64 tapers gradually to a sharp point 65. Shaft 64 is provided with a ring member 73 having a diameter which closely corresponds to the inner diameter of housing 62 to guide the travel of shaft 64 within housing 62. A compression spring 67 is interposed between the ring member 73 and the bottom of housing 62. Compression

spring 67 provides a bias force which normally urges the sharp point 65 into a retracted position within housing 62. The upper end of shaft 64 has an enlarged head 68 extending outside of the housing 62 which is intended to be manually depressed or struck by a percussion instrument in order to drive the sharp point 65 out of housing 62 and into a vertebral body 50a. Shaft 64 is given a length, taking into account the length that spring 67 will have when fully compressed, to determine the maximum depth of the pilot hole formed in a vertebral body. The depth is selected to assure that the pilot hole does not reach the posterior cortex of the vertebral body, which borders the spinal canal.

Certain structural features of hole forming apparatus 60 are shown in greater detail in FIG. 32. In particular, it can be seen that the bottom end of housing 62 has a projecting portion 69 dimensioned to fit precisely in a bone screw receiving hole 6 or 8 of plate 2. The bottom 71 of the projecting portion 69 is flat in a plane perpendicular to the axis of housing 62. When the projecting portion 69 of housing 62 is snugly inserted into a bone screw receiving hole 6, 8 and the flat bottom 71 is placed flush against the upper surface of plate 2, it is assured that the leading end 66 of shaft 64 will form a pilot hole in the vertebral bone having an axis perpendicular to the plane of the associated portion of plate 2, thereby assuring

that the bone screw 30 will be subsequently installed so that its axis is also perpendicular to the plane which is parallel to the upper and lower surfaces of the associated portion of plate 2.

When a plate is used which has a threaded bone screw receiving hole, the lower end of the pilot hole forming apparatus 60 is threaded so as to engage the thread in the bone screw receiving hole 6, 8 thereby fixing the plate and the pilot hole forming apparatus together, assuring a stable fit between the pilot hole forming apparatus and the plate 2. It should be noted that the diameter of the leading end 66 of the shaft 64 is small since it has to fit within the small space left between the inside wall of the pilot hole forming apparatus. Since it is only a pilot hole for a self-tapping bone screw 30 that is being formed, the small diameter is satisfactory.

Referring to FIG. 37, if for any reason it should be desired to form the pilot hole in the vertebral body 50 by drilling, rather than by the use of the pilot hole forming apparatus 60, use can be made of a drill guide 80, having a lower end as shown in FIG. 37. The drill 80 guide consists of a tubular member 82 and a small diameter lower end 84 which is dimensioned to achieve a precise interference fit in the associated bone screw receiving hole 6, 8 of plate 2. Along the small diameter lower end 84, drill guide 80 has an axial end surface in a plane perpendicular to the longitudinal axis of the

drill guide 80 so that when the small diameter portion 84 is fitted into the bone screw receiving hole 6 and the surface surrounding the small diameter portion 84 is flush against the upper surface of plate 2, the axis of the drill guiding bore 86 in drill guide 80 will be precisely perpendicular to the upper and lower surfaces of the associated portion of plate 2. As with the case described above, the bottom end of the drill guide 80 can be threaded so as to engage to the threaded opening of plate 2.

After the bone screw receiving holes 6, 8 are formed in the vertebral body 50a through the upper two bone screw securing holes 6 of plate 2 by means of either hole forming apparatus 60 or drill guide 80, bone screws 30 are threaded into the vertebrae 50 while holding the plate 2 firmly against the vertebrae 50 with compression tool 100 or plate holder 800. This locks the plate to the vertebrae 50a.

It is then possible, if desired, to compress the fusion graft in the next adjacent vertebrae 50b before attaching bone screws 30 to the adjacent vertebrae 50b through the central bone screw receiving holes of plate 2. Once the initial bone screws are in place in the vertebrae 50a, the plate holder 100 or 800 may be removed from the plate 2. The compression of the fusion graft construct between the two adjacent vertebrae 50a and 50b is achieved as follows:

Compression post 54 is driven through the central locking hole 12 of plate 2 by means of insertion tool 90, shown in FIGS. 33, 34 and 35, into the vertebral bone of vertebra 50b, where it will be used in a subsequent step to apply a compression force between vertebrae 50a and 50b. Compression post 54 consists of a shaft 56 having a sharp point 57 at its lower end, an enlarged central collar 58 which serves as a depth stop, and a circumferential groove 59 proximate its upper end, defining an enlarged head 55.

Compression post insertion tool 90 consists of a shaft 92 having a closed hollow portion 94 at its lower end 96 for receiving compression post 54 and an enlarged percussion cap 98 at its other end. Compression post insertion tool 90 also includes in its lower end 96 a second opening 95 having a recess 99 in its inside wall for permitting engagement of the enlarged head 55 on the compression post 54 within the depression 97. The second opening 95 is in communication with the hollow portion 94 of the insertion tool 90, as shown in FIG. 35.

Referring to FIG. 38, the bore 132 in the second compression arm 130 of compression tool 100 is then applied over compression post 54 in vertebrae 50b, and the plate engaging element 108 is inserted in the bore 106 of the first compression arm 104 of compression tool 100. The hook 110 of the plate engaging element 108 shown in FIG. 36 is fitted into the notch 18

at the end of the plate 2 which is fixed by the bone screws 30 inserted into the vertebra 50a, as shown in FIG. 38. As indicated above, however, the compression tool 100 can be rotated so that the first compression arm 104 is now at the bottom and is able to fit over the compression post 54 in vertebrae 50c.

Since the plate is attached to vertebrae 50a by means of bone screws 30 and compression post 64 is fixed to the adjacent vertebrae 50b, movement of the first and second compression arms 104 and 130 in the direction of vertebrae 50a by rotation of handle 140 results in compression of the bone graft construct 51 between the adjacent vertebrae 50a and 50b. The distance of several millimeters is sufficient for compression of the bone graft construct 51. Once the desired compression is obtained, bone screw pilot holes can be formed in vertebral body 50b by means of pilot hole forming apparatus 60, as described above, for insertion of bone screws 30 into bone screw receiving holes 8 of bone plate 2, fixing the plate 2 to the adjacent vertebrae 50b. Compression tool 100 can then be withdrawn by activation of the release.

FIG. 39 illustrates the use of compression tool 100 to induce compression between the lower two vertebral bodies 50b and 50c after bone screws 30 have been installed in the middle vertebral body 50b as just described. As shown in FIG. 39, compression post 54 remains in place in the middle vertebral body

[illegible]

post 54 by depression 97, as shown in FIG. 34.

It is recognized that other variations in the order of compression may be employed. For example, during the compression of the fusion graft construct 51 between vertebrae 50b and 50c, the hook 110 of compression tool 100 may engage the notch 18 in the end of the plate 2, and the other compression arm of the compression tool 100 may engage the compression post 54 in the third adjacent vertebrae 50c. It should also be noted that plate 2 has a recess end cut out portion between the lobes at the end of the plate for insertion of the compression post 54 in the vertebrae. Otherwise, there may not be room below the end of the plate 2 for insertion of the compression post 54.

It will be noted that the above-described procedure will be performed with the bone screws 30 fully inserted into vertebral bodies 50a, 50b and 50c and lordosis is maintained during compression of the bone graft construct 51.

As indicated above, the procedure for attaching the plate 2 to the vertebrae 50a, 50b and 50c was illustrated without the locking screws 20, 21 in place on the plate 2. FIG. 40 is a perspective view showing the plate 2 of FIGS. 1-5, at a stage of a surgical procedure when bone screws 30 have been fully installed in three adjacent vertebrae 50a, 50b and 50c, and locking screws 20, 21 have been rotated through an angle of about 90° to lock three bone screws 30 in place; the left-hand locking

screw 20 as viewed has been rotated through an angle of about 60° to lock three bone screws 30 in place and the central locking screw 21 has been rotated through an angle of about 90° to lock two other bone screws 30 in place. At this time, one of the camming surfaces 44 of each locking screw 20, 21 rests atop the screw head 32 of a respective bone screw 30.

Installation of the locking cap 300 can also be performed with a tool 220 such as shown in FIGS. 41 and 42 having a suitably shaped tip 222 with a length corresponding to the depth of hole 306 in a locking cap 300. The end 222 of tool 220 is flared just proximal to the most distal end so that it creates a friction fit with the screw cap 300 for ease of manipulation, and prevents the screw cap 300 from falling off the tool 200.

FIG. 43 is a cross-sectional view in the plane of the center of the two end locking screw holes 6 of plate 2, with two bone screws 30 in their installed positions and locking element 21 in its locking position. FIG. 44 is an enlarged view of one of the bone screws 30 in plate 2 of FIG. 43. In a preferred embodiment, the axis of each screw 30 is generally perpendicular to tangents to the upper and lower surfaces of plate 2 at points which are intersected by the longitudinal axis of the associated bone screw 30. Thus, because of the curvature of plate 2 in the plane of FIG. 18, bone screws 30 can be directed so as to converge toward one another at a desired angle. The axis of the

two bone screws 30 shown in FIG. 18 may subtend an angle of about 45°. Alternatively, the curvature of the plate from side to side may be so as to conform to the surface of the anterior aspect of the human adult cervical spine and the axis of the paired screw hole may deviate from being perpendicular to the plate when viewed on end to achieve optimal convergence.

Because the bone screws 30, once inserted, are locked to the plate, a "claw" of a rigid triangular frame structure is obtained at each pair of bone screws 30 such that the attachment of plate 2 to the vertebral bodies 50a, 50b and 50c would be highly secure due to the trapping of a wedged mass of bone material between the angled bone screws triangle, even if any thread stripping should occur. The "claw" may be further formed by three angled bone screws in a tripod configuration or by four bone screws in a four sided claw configuration.

A plating system according to each of the above embodiments can be installed in the same manner as described above, and using the same instruments and tools, as illustrated and described above with respect to the first embodiment. In the case of the embodiment shown in FIG. 22, the compression operations would be performed by means of slot 604 instead of the middle locking screw hole 12.

b.) The Single Locking Plate Systems

09618566-071700

The single locking plate system will now be described. FIGS. 47-52 are views of a first embodiment of a single locking plate system. The contour of plate 600 is the same as the plate 2 shown in FIGS. 1-5. Plate 600 contains bone screw receiving holes 602 which are internally threaded 603 for receiving corresponding locking elements in the form of a locking cap 610, shown in Figures 56-59. For example, in plate 600, the bone screw hole 602 has an outer diameter of approximately 5 mm with a preferred range of 4-6 mm; and a threaded inner diameter of approximately 4.8 mm, with a range of 3.5-5.8 mm for this use. Attaching means other than threads may be used, such as bayonet type attachment elements.

The bottom of each bone screw receiving hole 602 has an inwardly stepped portion of properly selected dimensions for retaining an associated bone screw 170, as shown in FIGS. 53-55. As described in greater detail below, in this embodiment, a single locking element in the form of a locking cap 610 having threads 608 shown in FIGS. 56-59, is associated with each of the bone screws receiving holes 602.

The difference between the bone screw 170 used in the single locking embodiment of the plate from the bone screw used in association with the multiple locking plate is essentially due to the fact that whereas in the multiple locking plate embodiment the locking elements slide over a portion of the top 39 of the

screw head 32, in the single locking embodiment the locking cap 610 fits over the head 172 of the bone screw 170. Therefore, the head 172 of the bone screw 170 of the present embodiment need not be smooth. This permits the head 172 of this embodiment bone screw 170 to be thicker and stronger.

FIG. 63 shows two bone screws 170 and associated threaded locking caps 610 in their fully installed positions. In these positions, head portions 174 and 176 of each bone screw 170 form an interference fit with corresponding portions of an associated bone screw receiving hole 602. Rim 612 of each threaded locking cap 610 forms an interference fit with upper portion 178 of the head of its associated bone screw 170. Because the thread 608 of each locking cap 610 mates precisely with the internal thread in an associated bone screw receiving hole 602, each threaded locking cap 610 is additionally subjected to a clamping force between associated head portion 178 and the internal threads 603 of associated bone screw receiving hole 602. The rounded head 614 of each threaded locking cap 610 assures that the upper surface of an assembled plating system will be free of sharp edges, or projections.

Referring to FIGS. 80 and 81 tools for use in inserting both the bone screws and the locking cap in the single locking plate 600 are shown. In the first embodiment of the driving tool 1000 shown in FIG. 80, the tool 1000 has an outer tubular

housing 1002. Within the housing 1002 is a torks type or hexagonal driver 1004 that has a projecting end 1006 that corresponds to the recess 306 in the cap 610 for engagement with the cap 610. As indicated above, the driver 1004 is configured so that it makes a firm attachment for the locking cap 610 for holding the locking cap 610 firmly to the driver. The hex driver 1004 is hollow so as to be able to permit the shaft 1010 of a Phillips or torks screw driver to fit through the hollow portion 1012 for engagement by its tip 1012 with the corresponding recess 180 of bone screw 170 for engagement by the end 1006 of the driver 1004. The shaft 1010 of the driver 1000 is longer than the tubular housing and driver 1004 has an upper end (not shown) extending from the top end of the tubular housing 1002 so that it can be rotated by the handle.

The housing 1002 has a diameter that permits the locking cap 610 to be held within the inner end of the tubular housing 1002 by a friction fit or to the driver 1004. It is appreciated that other methods of holding the locking cap 610 within the end of the tubular housing 1000 may also be employed.

As shown in Figure 80, the operation of the bone screw and locking element driver 1000 is as follows: the cap 610 is inserted onto the end of the cap driver 1004, and then the cap driver 1004 with the shaft 1010 of the bone screw driver passing through the central longitudinal opening of the cap driver. As

shown, the bone screw driver shaft 1010 passes through the recess 306 in the cap 610 and engages the recess 180 in the head of the bone screw 170. The bone screw 170 is shown being installed in a bone screw receiving hole in the plate 600. The handle (not shown) of the bone screw driver is rotated, thereby screwing the bone screw 170 in place. Since the diameter of the bone screw driver is less than the width of the recess 306 of the cap 610, the bone screw driver 1010 is able to rotate without rotation of the cap 610.

The hollow tubular housing 1002 rests on the top surface of the plate 600 and assists in the alignment of the shaft 1010 in relationship to the plate. Once the bone screw 170 is inserted, the cap driver 1004 is depressed until the threads 608 on the outside of the cap 610 engages the threads 603 of the bone screw receiving hole. The cap driver 1004 is then turned until the cap 610 is securely locked in place.

In FIG. 81, an alternative embodiment of the combination bone screw and locking cap driver is shown. In this embodiment, a housing is not used. Instead, the cap driver 1010 holds the cap 610 by friction and the handle 620 for the bone screw driver 1010 is rotated. A ball spring 622 assembly holds the cap driver 1002 up until the bone screw has been screwed into the bone screw receiving hole. Driver 1010 has an elongated portion that once the bone screw has been installed, the ball

spring 622 is depressed and the handle 624 associated with the cap driver is permitted to descend for rotation of the cap 610. A tubular housing can be employed to assist in aligning of the cap 610 in the bone screw receiving hole, as indicated above.

The drivers shown in FIGS. 80 and 81 simplify the procedure, and reduce the number of instruments that are necessary to be used during the installation procedure. The procedure is quick and reliable, giving the physician more assurance that small watch parts will not be lost or difficult to manipulate.

FIG. 52 is a top view of the plate 600 partially installed, with threaded locking caps 600 installed in bone screw receiving holes 602.

FIGS. 54-56 show a bone screw 170 for use with the single locking plating system according to the invention. Bone screw 170 differs from bone screw 30 previously described in detail, only with regard to the stepped configuration of head 172. Preferably, bone screw 170 includes a lower portion 174 which is contiguous with the screw shank and has a reduced diameter equal to the maximum diameter of the shank 176. Portion 178 of head 172 also has smaller diameter than lower portion 174. The thread 182 has the same configuration as for the bone screw 30 discussed above. However, either embodiment of bone screws can be used with any of the plates.

As in the case of the multiple locking plating system described above, the bone screws 170 for use in the single locking plating system are preferably solid, where the screws adjoin the lower plate surface, where screws used with prior art plates are most prone to breakage, the only recess in the heads being for engagement of the tip 222 of driving tool 220 and with the recess being above the critical area. Therefore, these bone screws 170 remain robust. The screw heads are not deeply slitted into portions and the locking caps do not impose a radial outer force on the associated bone screw heads so the screw heads do not spread apart so as to be stressed and weakened.

Referring to FIGS. 71, 73 and 75 another alternative embodiment of the single locking plate system of the present invention is shown and referred to by the number 500. The plate 500 has the same contour as the plate 2 shown in FIGS. 1-5, but associated with each of the bone screw openings 502, are threaded openings 524 offset from the bone screw openings 502 for receiving the locking element 506, 508, shown in FIGS. 72 and 74 as a threaded locking set screw or cap 506 or screw 508.

It is appreciated that other configurations of single locking plates may be employed. Referring to FIG. 82, a single locking plate 900 is shown in which there are a pair of bone screw receiving holes 910 at its ends 930 and a number of bone screw receiving holes 950 along the longitudinal axis of the

09618566 "071700

plate 900. The additional bone screw receiving holes 950 permit a single plate to be able to be aligned with a number of different sized vertebrae disc spaces, and bone fusion grafts. As indicated above, the plate of the present invention shown in FIGS. 1-5, requires that a properly sized plate be selected by the surgeon so that each pair of bone screw receiving holes 6, 8 line up with the appropriate vertebrae. This requires a number of different sized plates to be available for optimum attachment of the bone screw receiving holes to each of the vertebrae. With the plate 900 of FIG. 82, the close spacing and increased number of central openings permit the surgeon to locate at least one appropriate opening to be aligned with each of the intermediate vertebrae, and/or bone grafts.

The procedure for installation of the single locking plates is substantially the same as described herein in detail for the multiple locking plates. The central longitudinal slot 670 in the single locking plates is used for the compression procedure. The same instrumentation is used to create the plate hole either by means of a punch or a drill. Figures 60-69 show the various steps in the procedure for installation of the single locking plates, comparable to the steps employed in the installation of the multiple locking plates.

Referring to FIGS. 76-79 the heads 507 and 526 of the locking elements 508 and 522 have a recess 510 and 524

corresponding to the radius of the bone screw openings 502 and 528 so that the locking element 508 and 522 may be installed in place prior to the insertion of the bone screw 170 into the bone screw receiving hole 502 and 528. When the locking elements 508 and 522 are rotated, a portion of its head extends over the top of the head of bone screw 170 to lock it in place. As with the above embodiments, the bottom surface of the locking screws 508 and 522 can have a camming or other configuration for engagement with the top surface 39 of the associated bone screw 170.

While the plate instrumentation and method have been described in association with attaching a plate to the vertebrae of the spine, it should be appreciated that the plates can be adopted for specification to other parties of the body. However, the dimensions of the plate, the specific contours and placement of the bone screw receiving holes would have to be modified.

Similarly, the bone screws described in this application could be used in other parts of the body, again being modified so as to serve their intended purposed, depending on the size of the body part in which they are to be installed.

While particular embodiments of the present invention have been shown and described, it will be obvious to those skilled in the art that changes and modifications may be made without departing from this invention in its broader aspects and, therefore, the aim in the appended claims is to cover all such

changes and modifications as fall within the true spirit and scope of this invention.

While specific innovative features may have been presented in reference to specific examples, they are just examples, and it should be understood that various combinations of these innovative features beyond those specifically shown are taught such that they may now be easily alternatively combined and are hereby anticipated and claimed.

004T20"8958T950

What is claimed is:

1. An anterior cervical plate for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said plate having a length sufficient to span at least two adjacent cervical vertebrae, a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface, said plate having a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface, said plate having at least a first pair of bone screw receiving holes associated with a first of the adjacent cervical vertebrae and at least a second pair of bone screw receiving holes associated with a second of the adjacent cervical vertebrae, said plate having a length longer than its width, wherein said lower surface of said plate has a first concave curvature parallel to said length, said first concave curvature having a radius of curvature between approximately 20 cm to 24 cm.

2. The plate of claim 1 in which said lower surface has a second concave curvature transverse to said length parallel to said width, said second concave curvature having a radius of curvature between approximately 15mm to 20mm.

3. The plate of claim 1 in which said plate has a generally rectangular configuration with lobes extending from at least the corners of said plate and has at least one of said bone

screw receiving holes located within one of said lobes.

4. The plate of claim 1 in which said plate has a length longer than said width.

5. The plate of claim 2 in which said second concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

6. The plate of claim 1 in which said plate has a length sufficient to span at least three consecutive vertebrae.

7. The plate of claim 1 in which said lower surface of said plate has a complex concave curvature configured to mate with the vertebral bodies of the at least two vertebrae, and each bone screw receiving hole has a longitudinal axis that is generally perpendicular to said lower surface at the location of said bone screw receiving hole and each of said bone screw receiving holes is formed to retain a respective bone screw in a position in which the longitudinal axis of said respective bone screw is aligned with the longitudinal axis of said bone screw receiving hole.

8. The plate of claim 1 further comprising a plurality of bone screws each insertable into a respective one of said bone screw receiving holes in a direction from said upper surface to said lower surface to secure said plate to a vertebra, each of said bone screws retainable in a respective one of said bone screw receiving holes below said upper surface.

9. The plate of claim 8 in which each of said bone screws has a head dimensioned to achieve an interference fit with a respective one of said bone screw receiving holes.

10. The plate of claim 8 in which said bone screws are self-tapping.

11. The plate of claim 8 in which each of said bone screws has a tip remote from said head, a shank which is tapered from said head to said tip, and a thread having a substantially constant crest diameter over substantially the length of said shank.

12. The plate of claim 11 in which said thread of each of said bone screws has a thin profile and a sharp crest.

13. The plate of claim 8 in which said bone screws are convergent.

14. The plate of claim 1 in which at least a portion of said lower surface comprises a bone ingrowth material.

15. The plate of claim 1 in which at least a portion of said lower surface comprises a bone growth material.

16. The plate of claim 1 in which at least a portion of said plate is coated with a material to induce the formation of bone.

17. The plate of claim 1 in which said plate comprises bone morphogenetic protein.

18. The plate of claim 1 in which at least a portion

of said plate is made of a material which is resorbable.

19. The plate of claim 18 in which said resorbable material is polygyconate.

20. The plate of claim 19 in which said resorbable material is impregnated with a fusion promoting substance.

21. The plate of claim 1 in which at least a portion of said lower surface is textured so as to promote bone ingrowth.

22. The plate of claim 21 in which said textured portion is impregnated with a fusion promoting substance.

23. The plate of claim 1 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

24. The plate of claim 1 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

25. The plate of claim 1 in which said plate includes an aperture proximate at least one of said bone screw receiving holes.

26. The plate of claim 25 in which said aperture comprises a slot along the longitudinal axis of said plate.

27. The plate of claim 1 in which at least at one end of said plate includes means for engaging a compression tool.

28. The plate of claim 27 in which said engaging means comprises a recess.

29. The plate of claim 28 in which said engaging means comprises a depression in said at least one end of said plate.

30. An anterior cervical plate for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said plate having a length sufficient to span at least two adjacent cervical vertebrae, a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface, said plate having a plurality of paired bone screw receiving holes extending through said plate from said upper surface to said lower surface, each pair of said bone screw receiving holes being adapted to be placed in the same vertebra, said plate having a length longer than its width, wherein said lower surface of said plate has a concave radius of curvature parallel to its width in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle to each other in the range of approximately 15 degrees to 30 degrees.

31. The plate of claim 30 in which at least one of said pairs of bone screw receiving holes form an included angle of approximately 20 degrees.

32. The plate of claim 30 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of less than approximately 29 degrees and greater than 21

degrees.

33. The plate of claim 30 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

34. The plate of claim 30 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

35. The plate of claim 30 in which each bone screw receiving hole is generally perpendicular to said lower surface of said plate.

36. The plate of claim 30 in which said increased upper portion of said bone screw receiving holes has a threaded portion.

37. The plate of claim 30 further comprising a thread on the interior of one of said bone screw receiving holes.

38. The plate of claim 30 in which at least one of said bone screw receiving holes has means for preventing a bone screw from passing entirely through said one of bone screw receiving holes.

39. The plate of claim 30 in which at least one of said bone screw receiving holes has an upper diameter portion and a smaller lower diameter portion to prevent a bone screw being

placed in said one of bone screw receiving holes from passing entirely through said one of bone screw receiving holes.

40. The plate of claim 30 in which at least a portion of said lower surface comprises a bone growth material.

41. The plate of claim 30 in which at least a portion of said plate is coated with a material to induce the formation of bone.

42. The plate of claim 30 in which said plate comprises bone morphogenetic protein.

43. The plate of claim 30 in which at least a portion of said plate is made of a material which is resorbable.

44. The plate of claim 43 in which said resorbable material is polygyconate.

45. The plate of claim 44 in which said resorbable material is impregnated with a fusion promoting substance.

46. The plate of claim 30 in which at least a portion of said lower surface is textured so as to promote bone growth.

47. The plate of claim 46 in which said textured portion is impregnated with a fusion promoting substance.

48. The plate of claim 30 in which at least a portion of said lower surface comprises a time released bone growth material.

49. The plate of claim 30 in which at least a portion of said lower surface is roughened to promote the growth of bone

along said lower surface.

50. The plate of claim 30 in which said plate includes an aperture between said first end and said second end proximate at least one of said bone screw receiving holes.

51. The plate of claim 50 in which said aperture comprises a slot along the longitudinal axis of said plate.

52. The plate of claim 30 in which at least at one end of said plate includes means for engaging a compression tool.

53. The plate of claim 52 in which said engaging means comprises a recess.

54. The plate of claim 52 in which said engaging means comprises a depression in said at least one end of said plate.

55. An anterior cervical plate for engaging a human cervical spine along the anterior aspect of the spine, said plate having a first end, a second end, and a length sufficient to span at least three adjacent cervical vertebrae, said plate having a lower surface for contacting the adjacent cervical vertebrae and an upper surface opposite to said lower surface, said plate having at least a first pair of bone screw receiving holes associated with a first of the adjacent cervical vertebrae and at least a second pair of bone screw receiving holes associated with a second of the adjacent cervical vertebrae, said plate having at least one transverse pair of intermediate bone screw receiving holes associated with a cervical vertebrae intermediate the first

and second of the adjacent cervical vertebrae, each of said bone screw receiving holes extending through said plate from said upper surface to said lower surface, and said plate having an aperture there through between said first and second pairs of bone screw receiving holes, said aperture being associated with the intermediate cervical vertebrae.

56. The plate of claim 55 in which said plate has a length longer than said width, and said lower surface has a concave curvature parallel to said length, said concave curvature having a radius of curvature greater than 15 cm and less than 25 cm.

57. The plate of claim 55 in which said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

58. The plate of claim 57 in which said first concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

59. The plate of claim 55 in which said lower surface of said plate has a complex concave curvature configured to mate with the vertebral bodies of the at least two vertebrae, and each bone screw receiving hole has a longitudinal axis that is generally perpendicular to said lower surface at the location of said bone screw receiving hole and each of said bone screw receiving holes is formed to retain a respective bone screw in a

position in which the longitudinal axis of said respective bone screw is aligned with the longitudinal axis of said bone screw receiving hole.

60. The plate of claim 55 in which said plate has a generally rectangular configuration with lobes extending from at least the corners of said plate and has at least one of said bone screw receiving holes located within one of said lobes.

61. The plate of claim 55 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

62. The plate of claim 55 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

63. The plate of claim 55 in which at least a portion of said lower surface comprises a bone growth material.

64. The plate of claim 55 in which at least a portion of said lower surface comprises a bone ingrowth material.

65. The plate of claim 55 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

66. The plate of claim 55 in which at least a portion of said lower surface comprises a bone growth material.

67. The plate of claim 55 in which at least a portion of said plate is coated with a material to induce the formation of bone.

68. The plate of claim 55 in which said plate comprises bone morphogenetic protein.

69. The plate of claim 55 in which at least a portion of said plate is made of a material which is resorbable.

70. The plate of claim 69 in which said resorbable material is polygyconate.

71. The plate of claim 69 in which said resorbable material is impregnated with a fusion promoting substance.

72. The plate of claim 55 in which at least a portion of said lower surface is textured so as to promote bone ingrowth.

73. The plate of claim 72 in which said textured portion is impregnated with a fusion promoting substance.

74. The plate of claim 55 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

75. The plate of claim 55 in which at least a portion of said lower surface is roughened to induce the formation of bone along at least a portion of said lower surface.

76. The plate of claim 55 in which said aperture comprises a slot along the longitudinal axis of said plate.

77. The plate of claim 55 in which at least at one

end of said plate includes means for engaging a compression tool.

78. The plate of claim 77 in which said engaging means comprises a recess.

79. An anterior cervical plate for engaging a human cervical spine along the anterior aspect of the spine, said plate having a length sufficient to span at least two adjacent cervical vertebrae, said plate having a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface, said plate having at least a first pair of bone screw receiving holes associated with a first of two adjacent cervical vertebrae and at least a second pair of bone screw receiving holes associated with a second of the two adjacent vertebrae, said bone screw receiving holes extending through said plate from said upper surface to said lower surface, and at least one end of said plate including a recess for engaging a compression tool.

80. The plate of claim 79 in which said engaging means comprises a recess.

81. The plate of claim 79 in which said plate includes an aperture along a transverse line intermediate said first and said second pairs of bone screw receiving holes.

82. The plate of claim 79 wherein said plate has a length longer than said width, and said lower surface has a concave curvature parallel to said length, said concave curvature having a radius of curvature greater than 15 mm and less than 25

cm.

83. The plate of claim 79 in which said plate has a generally rectangular configuration with lobes extending from at least the corners of said plate and has at least one of said bone screw receiving holes located within one of said lobes.

84. The plate of claim 79 in which said plate has a length longer than said width, and said lower surface has a concave curvature parallel to said width.

85. The plate of claim 84 in which said concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

86. The plate of claim 79 in which said plate has a length sufficient to span at least three consecutive vertebrae.

87. The plate of claim 79 in which said lower surface of said plate has a complex concave curvature configured to mate with the vertebral bodies of the at least two vertebrae, and each bone screw receiving hole has a longitudinal axis that is generally perpendicular to said lower surface at the location of said bone screw receiving hole and each of said bone screw receiving holes is formed to retain a respective bone screw in a position in which the longitudinal axis of said respective bone screw is aligned with the longitudinal axis of said bone screw receiving hole.

88. The plate of claim 79 in which the central

longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of approximately 20 degrees to 30 degrees.

89. The plate of claim 79 in which the central longitudinal axes of the bone screw receiving holes of said pairs of bone screw receiving holes form an included angle of greater than 30 degrees.

90. The plate of claim 79 further comprising at least one bone screw receiving hole associated with a cervical vertebrae intermediate the first and second of the adjacent vertebrae.

91. The plate of claim 79 wherein at least a portion of said lower surface comprises a bone ingrowth material.

92. The plate of claim 79 in which at least a portion of said lower surface comprises a bone growth material.

93. The plate of claim 79 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

94. The plate of claim 79 in which at least a portion of said plate is coated with a material to induce the formation of bone.

95. The plate of claim 79 in which said plate comprises bone morphogenetic protein.

96. The plate of claim 79 in which at least a portion

of said plate is made of a material which is resorbable.

97. The plate of claim 96 in which said resorbable material is polygyconate.

98. The plate of claim 96 in which said resorbable material is impregnated with a fusion promoting substance.

99. The plate of claim 79 in which at least a portion of said lower surface is textured so as to promote bone ingrowth.

100. The plate of claim 99 in which said textured portion is impregnated with a fusion promoting substance.

101. The plate of claim 79 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

102. An anterior cervical plate for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said plate having a length sufficient to span at least two adjacent cervical vertebrae, a lower surface for contacting the adjacent cervical vertebrae and an upper surface opposite to said lower surface, said plate having a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface, at least a first of said bone screw receiving holes being associated with a first of the adjacent cervical vertebrae and at least a second of said bone screw receiving holes being associated with a second of the adjacent cervical vertebrae, at least one of said bone screw

09618566-07100

receiving holes having a recess associated with and partially offset therefrom, and a locking element associated with said recess having a head, said locking element capable of being pre-installed to said plate prior to insertion of a bone screw into said at least one bone screw hole, said locking element being movable from a first position to a second position, said head being configured so as to permit insertion of bone screws into said bone screw receiving hole associated with said recess when in said first position and so as to cover at least a portion of a bone screw inserted in said bone screw receiving hole associated with said recess when said locking element is in said second position.

103. The plate of claim 102 in which said locking element has a bearing surface for bearing against a portion of a bone screw when said locking element is in said second position.

104. The plate of claim 102 in which said locking element has at least one camming surface.

105. The plate of claim 102 in which said locking element has at least one ramped surface.

106. The plate of claim 102 in which said recess has a threaded portion.

107. The plate of claim 106 in which said locking element comprises a threaded member.

108. The plate of claim 106 in which said locking

element has a camming surface.

109. The plate of claim 106 in which said locking element has a ramped surface.

110. The plate of claim 106 in which said locking element comprises a screw having a head portion and a threaded shaft.

111. The plate of claim 106 in which said head has a camming surface.

112. The plate of claim 106 in which said head has a ramped portion surface.

113. The plate of claim 102 in which said locking element comprises a rivet.

114. The plate of claim 113 in which said rivet has a camming surface.

115. The plate of claim 113 in which said rivet has a ramped surface.

116. The plate of claim 102 in which said recess has at least one camming surface for cooperation with said locking element.

117. The plate of claim 116 in which said locking element has a camming surface.

118. The plate of claim 102 in which said removed segment is arcuate and has the same or greater radius of curvature than the corresponding bone screw receiving hole.

119. The plate of claim 102 further comprising an opening in the side wall of said bone screw receiving hole in communication with the side wall of said recess, said locking element having a projection to fit within said opening so as to cover a portion of said bone screw receiving hole when said locking element is moved from said first position to said second position.

120. The plate of claim 119 in which said projection has a ramped surface.

121. The plate of claim 102 in which said locking element is permanently attached to said plate.

122. The plate of claim 102 in which said head has at least one segment removed therefrom.

123. The plate of claim 102 in which said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

124. The plate of claim 123 in which said first concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

125. The plate of claim 102 in which said lower surface of said plate has a second concave curvature parallel to said length.

126. The plate of claim 125 wherein said second concave curvature has a radius of curvature greater than 15 cm

and less than 25 cm.

127. The plate of claim 102 in which said plate has a generally rectangular configuration with lobes extending from at least the corners of said plate and has at least one of said bone screw receiving holes located within the circumference of at one of said lobes.

128. The plate of claim 102 in which said plate has a length sufficient to span at least three consecutive vertebrae.

129. The plate of claim 102 in which the central axes of said bone screw receiving holes are perpendicular to said lower surface of said plate.

130. The plate of claim 102 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

131. The plate of claim 102 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

132. The plate of claim 102 in which at least one of said bone screw receiving holes has means for preventing a bone screw from passing entirely through said one of bone screw receiving holes.

133. The plate of claim 102 in which at least one of

said bone screw receiving holes has an upper diameter portion and a smaller lower diameter portion to prevent a bone screw being placed in said one of bone screw receiving holes from passing entirely through said one of bone screw receiving holes.

134. The plate of claim 102 in which at least a portion of said lower surface comprises a bone ingrowth material.

135. The plate of claim 102 in which at least a portion of said lower surface comprises a bone growth material.

136. The plate of claim 102 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

137. The plate of claim 102 in which at least a portion of said plate is coated with a material to induce the formation of bone.

138. The plate of claim 102 in which said plate comprises bone morphogenetic protein.

139. The plate of claim 102 in which at least a portion of said plate is made of a material which is resorbable.

140. The plate of claim 139 in which said resorbable material is polygyconate.

141. The plate of claim 139 in which said resorbable material is impregnated with a fusion promoting substance.

142. The plate of claim 102 in which at least a portion of said lower surface is textured so as to promote bone ingrowth.

recess for receiving a locking element;

a plurality of bone screws each insertable into a respective one of said bone screw receiving holes in a direction from said upper surface to said lower surface to secure said plate to a vertebra, each of said bone screws retainable in a respective one of said bone screw receiving holes; and

a plurality of locking elements each engageable in a respective one of said offset recesses associated with said bone screw receiving holes, said plurality of locking elements each being configured to lock one of said bone screws to said plate by covering at least a portion of one of said bone screw receiving holes below said upper surface.

148. The plate system of claim 147 in which said locking element has a bearing surface for bearing against a portion of a bone screw when said locking element is in said second position.

149. The plate system of claim 147 in which said locking element has a camming surface.

150. The plate system of claim 147 in which said locking element has a ramped surface.

151. The plate system of claim 147 in which said recess has a threaded portion.

152. The plate system of claim 151 in which said locking element comprises a threaded portion.

153. The plate system of claim 152 in which said locking element has a camming surface.

154. The plate system of claim 152 in which said locking element has a ramped surface.

155. The plate system of claim 151 in which said locking element comprises a screw having a head portion and a threaded shaft.

156. The plate system of claim 155 in which said screw has a camming surface.

157. The plate system of claim 155 in which said screw has a ramped surface.

158. The plate system of claim 147 in which said locking element comprises a rivet.

159. The plate system of claim 158 in which said rivet has a camming surface.

160. The plate system of claim 158 in which said rivet has a ramped surface.

161. The plate system of claim 147 in which said recess has at least one camming surface for cooperation with said locking element.

162. The plate system of claim 161 in which said locking element has a camming surface.

163. The plate system of claim 147 in which said locking element has a removed segment that is arcuate and has the

same or greater radius of curvature than the corresponding bone screw receiving hole.

164. The plate system of claim 147 further comprising an opening in the side wall of one of said bone screw receiving hole in communication with the side wall of said recess, said locking element having a projection adapted to fit within said side wall opening so as to cover a portion of said one of said bone screw receiving hole when said locking element is moved from a first position to a second position.

165. The plate system of claim 164 in which said projection has a ramped surface.

166. The plate system of claim 147 in which said locking element is permanently attached to said plate.

167. The plate system of claim 147 in which at least one end of said plate has a means for removably engaging a compression tool.

168. The plate system of claim 167 in which said engaging means comprises a depression in said at least one end of said plate.

169. The plate system of claim 147 in which said recess for receiving a locking element comprises a thread on the interior of at least one of said bone screw receiving holes.

170. The plate system of claim 147 in which said locking element covers at least a portion said bone screw

receiving hole when placed in said recess.

171. The plate system of claim 147 in which said plate has a width and length longer than said width, and said lower surface has a first concave curvature parallel to said width.

172. The plate system of claim 171 in which said first concave curvature has a radius of curvature of the order of approximately 16-21 mm.

173. The plate system of claim 171 in which said lower surface of said plate has a second concave curvature parallel to said length.

174. The plate system of claim 173 in which said second concave curvature has a radius of curvature greater than 15 cm and less than 25 cm.

175. The plate system of claim 147 in which said plate has a generally rectangular configuration, has lobes extending from at least the corners of said plate, and has at least one of said bone screw receiving holes located within the circumference of said lobes.

176. The plate system of claim 147 in which said plate has a length sufficient to span at least three consecutive vertebrae.

177. The plate system of claim 147 in which the central axes of said bone screw receiving holes are perpendicular to said lower surface of said plate.

178. The plate system of claim 147 in which each of said bone screws have a head dimensioned to achieve an interference fit with a respective one of said bone screw receiving holes.

179. The plate system of claim 147 in which said bone screw and said locking element have heads with means for engaging a tool for rotating said bone screws and said locking element.

180. The plate system of claim 147 in which each of said bone screws has a head and a first irregular depression in the top of said head, and said locking element has a head portion and a second irregular depression in said head, both of said first and second depressions having the same cross section.

181. The plate system of claim 147 in which each of said bone screws are self-tapping.

182. The plate system of claim 147 in which each of said bone screws has a tip remote from said head, a shank which is tapered from said head to said tip, and a thread having a substantially constant crest diameter over substantially the length of said shank.

183. The plate system of claim 182 in which said thread of each of said bone screws has a thin profile and a sharp crest.

184. The plate system of claim 147 in which said bone screws and said locking element do not project above the upper

surface of said plate when said plate is installed.

185. The plate system of claim 147 in which at least one of said bone screw receiving holes has means for preventing a bone screw from passing through said bone screw receiving hole.

186. The plate system of claim 147 in which each of said bone screw receiving holes has an upper diameter portion and a smaller lower diameter portion to prevent a bone screw being placed in said bone screw receiving hole from passing through said bone screw receiving hole.

187. The plate system of claim 147 in which at least a portion of said lower surface comprises a bone growth material.

188. The plate system of claim 147 in which at least a portion of said plate is coated with a material to induce the formation of bone.

189. The plate system of claim 147 in which said plate comprises bone morphogenetic protein.

190. The plate system of claim 147 in which at least a portion of said plate is made of a material which is resorbable.

191. The plate system of claim 190 in which said resorbable material is polygyconate.

192. The plate system of claim 190 in which said resorbable material is impregnated with a fusion promoting substance.

193. The plate system of claim 147 in which at least a

portion of said lower surface is textured so as to induce bone ingrowth.

194. The plate system of claim 193 in which said textured portion is impregnated with a fusion promoting substance.

195. The plate system of claim 147 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

196. The plate system of claim 147 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

197. The plate system of claim 147 in which at least one end of said plate has means for removably engaging the first end of a compression tool.

198. The plate system of claim 197 in which said engaging means comprises a depression in said at least one end of said plate.

199. The plate system of claim 197 in which said opening comprises a longitudinal slot along the longitudinal axis of said plate.

200. An anterior cervical plate for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said plate having a length sufficient to span at least two adjacent cervical vertebrae, a lower surface for

length.

205. The plate of claim 204 in which said second concave curvature has a radius of curvature greater than approximately 15 cm and less than approximately 25 cm.

206. The plate of claim 200 in which said plate has a generally rectangular configuration with lobes extending from at least the corners of said plate and has at least one of said bone screw receiving holes located within the circumference of said lobes.

207. The plate of claim 200 in which said lower surface of said plate has a complex concave curvature configured to mate with the vertebral bodies of the at least two vertebrae, and each bone screw receiving hole has a longitudinal axis that is generally perpendicular to said lower surface at the location of said bone screw receiving hole and each of said bone screw receiving holes is formed to retain a respective bone screw in a position in which the longitudinal axis of said respective bone screw is aligned with the longitudinal axis of said bone screw receiving hole.

208. The plate of claim 200 in which said increased upper portion of said bone screw receiving holes has a threaded portion.

209. The plate of claim 200 further comprising a thread on the interior of one of said bone screw receiving hole.

210. The plate of claim 200 in which at least one of said bone screw receiving holes has means for preventing a bone screw from passing entirely through said one of bone screw receiving holes.

211. The plate of claim 200 in which at least one of said bone screw receiving holes has an upper diameter portion and a smaller lower diameter portion to prevent a bone screw being placed in said one of bone screw receiving holes from passing entirely through said one of bone screw receiving holes.

212. The plate of claim 200 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

213. The plate of claim 200 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

214. The plate of claim 200 in which said locking element comprises a cap.

215. The plate of claim 200 in which said locking element covers at least a portion of one of said bone screw receiving holes.

216. The plate of claim 200 in which each of said bone screws have a head dimensioned to achieve an interference fit

with a respective one of said bone screw receiving holes.

217. The plate of claim 200 in which said bone screws and said locking element each have a head with means for engagement by the same tool for rotating said bone screw and said locking element.

218. The plate of claim 200 in which each of said bone screws has a head with an irregular depression in the top of said head and said locking element has a head portion with an irregular depression, both of said depressions having the same cross sectional area.

219. The plate of claim 200 in which each of said bone screws is a self-tapping screw.

220. The plate of claim 200 in which each of said bone screws has a tip remote from said head, a shank which is tapered from said head to said tip, and a thread having a substantially constant crest diameter over most of the length of said shank.

221. The plate of claim 220 in which said thread of each of said bone screws has a thin profile and a sharp crest.

222. The plate of claim 200 in which said bone screws and said locking element do not project above the upper surface of said plate when said plate is installed.

223. The plate of claim 200 in which the central axes of said bone screw receiving holes are perpendicular to said lower surface of said plate.

235. The plate of claim 200 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

236. The plate of claim 200 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

237. The plate of claim 200 in which said plate includes an aperture between said first end and said second end proximate at least one of said bone screw receiving holes.

238. The plate of claim 237 in which said aperture comprises a slot along the longitudinal axis of said plate.

239. The plate of claim 200 in which at least one end of said plate has means for removably engaging the first end of a compression tool.

240. The plate of claim 239 in which said engaging means comprises a depression in said at least one end of said plate.

241. An anterior cervical plate system for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said system comprising:

a plate having a length sufficient to span at least two adjacent cervical vertebrae, a lower surface for contacting the adjacent cervical vertebrae, and an upper surface opposite to said lower surface;

a plurality of bone screw receiving holes associated with at least a first and a second of the adjacent cervical vertebrae, said plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface, at least one of said plurality of bone screw receiving holes having a reduced diameter lower portion and an increased diameter upper portion proximate said upper surface;

a plurality of bone screws each having a longitudinal axis for insertion into a respective one of said plurality of bone screw receiving holes in a direction from said upper surface to said lower surface and having a head for engaging said plate below said upper surface to secure said plate to a vertebra; and

a locking element engageable in said increased diameter upper portion of one of said bone screw receiving holes to lock one of said bone screws to said plate.

242. The plate system of claim 241 in which said recess has a threaded portion.

243. The plate system of claim 241 in which said locking element comprises a cap.

244. The plate system of claim 241 in which said locking element covers at least a portion of one of said bone screw receiving holes.

245. The plate system of claim 241 in which said locking element is coaxially engageable to one of said bone screw

receiving holes.

246. The plate system of claim 241 in which said plate has a length sufficient to span at least three consecutive cervical vertebrae.

247. The plate system of claim 245 in which said plate includes an aperture between said first end and said second end proximate at least one of said bone screw receiving holes.

248. The plate system of claim 247 in which said aperture comprises a slot along the longitudinal axis of said plate.

249. The plate system of claim 241 in which said plate has a length longer than said width, and said lower surface has a concave curvature parallel to said width.

250. The plate system of claim 249 in which said concave curvature has a radius of curvature in the order of approximately about 16-21 mm.

251. The plate system of claim 241 in which said lower surface of said plate has a concave curvature parallel to said length.

252. The plate system of claim 251 in which said concave curvature has a radius of curvature approximately 15 cm and less than approximately 25 cm.

253. The plate system of claim 241 in which said plate has a generally rectangular configuration with lobes extending

from at least the corners of said plate and has at least one of said bone screw receiving holes located within the circumference of said lobes.

254. The plate system of claim 241 in which said lower surface of said plate has a complex concave curvature configured to mate with the vertebral bodies of the at least two vertebrae, and each bone screw receiving hole has a longitudinal axis that is generally perpendicular to said lower surface at the location of said bone screw receiving hole and each of said bone screw receiving holes is formed to retain a respective bone screw in a position in which the longitudinal axis of said respective bone screw is aligned with the longitudinal axis of said bone screw receiving hole.

255. The plate system of claim 241 in which each of said bone screws have a head dimensioned to achieve an interference fit with a respective one of said bone screw receiving holes.

256. The plate system of claim 241 in which said bone screws and said locking element each have a head with means for engagement by the same tool for rotating said bone screw and said locking element.

257. The plate system of claim 241 in which each of said bone screws has a head with an irregular depression in the top of said head and said locking element has a head portion with

an irregular depression, both of said depressions having the same cross sectional area.

258. The plate system of claim 241 in which each of said bone screws is a self-tapping screw.

259. The plate system of claim 241 in which each of said bone screws has a tip remote from said head, a shank which is tapered from said head to said tip, and a thread having a substantially constant crest diameter over most of the length of said shank.

260. The plate system of claim 259 in which said thread of each of said bone screws has a thin profile and a sharp crest.

261. The plate system of claim 241 in which said bone screws are convergent.

262. The plate system of claim 241 in which said bone screws and said locking element do not project above the upper surface of said plate when said plate is installed.

263. The plate system of claim 241 in which said increased diameter upper portion for retaining a locking element comprises a thread on the interior of one of said bone screw receiving hole.

264. The plate system of claim 241 in which at least one of said bone screw receiving holes has means for preventing a bone screw from passing entirely through said one of bone screw

receiving holes.

265. The plate system of claim 241 in which at least one of said bone screw receiving holes has an upper diameter portion and a smaller lower diameter portion to prevent a bone screw being placed in said one of bone screw receiving holes from passing entirely through said one of bone screw receiving holes.

266. The plate system of claim 241 in which the central axes of said bone screw receiving holes are perpendicular to said lower surface of said plate.

267. The plate system of claim 241 in which at least a portion of said lower surface comprises a bone ingrowth material.

268. The plate system of claim 241 in which at least a portion of said lower surface comprises a bone growth material.

269. The plate system of claim 241 in which at least a portion of said plate is coated with a material to induce the formation of bone.

270. The plate system of claim 241 in which said plate comprises bone morphogenetic protein.

271. The plate system of claim 241 in which at least a portion of said plate is made of a material which is resorbable.

272. The plate system of claim 271 in which said resorbable material is polygyconate.

273. The plate system of claim 271 in which said resorbable material is impregnated with a fusion promoting

substance.

274. The plate system of claim 241 in which at least a portion of said lower surface is textured so as to induce bone ingrowth.

275. The plate system of claim 274 in which said textured portion is impregnated with a fusion promoting substance.

276. The plate system of claim 241 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

277. The plate of claim 241 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

278. The plate system of claim 241 in which said plate includes an aperture between said first end and said second end proximate at least one of said bone screw receiving holes.

279. The plate system of claim 278 in which said aperture comprises a slot along the longitudinal axis of said plate.

280. The plate system of claim 241 in which at least one end of said plate has means for removably engaging the first end of a compression tool.

281. The plate system of claim 280 in which said engaging means comprises a depression in said at least one end of

said plate.

282. An anterior cervical plate system for engaging at least three vertebrae of a human cervical spine along the anterior aspect of the spine, said device comprising:

a plate having a generally rectangular configuration with a first end, a second end, sides, and a length sufficient to span at least two adjacent cervical vertebrae, said plate having:

rounded lobes at each corner of said generally rectangular configuration and having rounded lobes on said sides between said first and second ends;

a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface;

a bi-concave curvature for conforming to the anterior aspect of the cervical spine in lordosis, said bi-concave curvature having a longitudinal concave curvature along the longitudinal axis of said plate and a transverse concave curvature along the transverse axis of said plate;

a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface and having a reduced diameter portion near said lower surface, a respective one of said plurality of bone screw receiving holes located at each of said rounded lobes such that said plate has a first pair of said bone screw receiving holes located at said first end of said plate

corresponding to a first of the adjacent vertebrae, a second pair of said bone screw receiving holes corresponding to a second of the adjacent vertebrae, and a third pair of said bone screw receiving holes corresponding to a third of the adjacent vertebrae; and

a plurality of locking elements for locking a bone screw placed in said bone screw receiving holes, each of said plurality of locking elements coaxially engageable in a respective one of said bone screw receiving holes to lock a bone screw to said plate, each of said locking elements having a bottom surface and a top surface with a depression for engaging a tool used to lock and unlock said locking element to said plate, said bottom surface configured to fit over the bone screw and bear against the bone screw.

283. The plate system of claim 282 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

284. The plate system of claim 282 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

285. The plate system of claim 282 in which said plate has a length longer than said width, and said lower surface has

concave curvature parallel to said length, said concave curvature having a radius of curvature greater than 15 cm and less than 25 cm.

286. The plate system of claim 282 in which said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

287. The plate system of claim 282 in which said first concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

288. The plate system of claim 287 in which said lower surface of said plate has a second concave curvature parallel to said length.

289. The plate system of claim 288 wherein said second concave curvature has a radius of curvature greater than 15 cm and less than 25 cm.

290. The plate system of claim 282 in which said locking element comprises a cap.

291. An anterior cervical plating system for engaging at least three vertebrae of a human cervical spine along the anterior aspect of the spine, said device comprising:

a plate having a generally rectangular configuration with a first end, a second end, sides, and a length sufficient to span at least two adjacent cervical vertebrae, said plate having:
rounded lobes at each corner of said generally

rectangular configuration and having rounded lobes on said sides between said first and second ends;

a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface;

a bi-concave curvature for conforming to the anterior aspect of the cervical spine in lordosis, said bi-concave curvature having a longitudinal concave curvature along the longitudinal axis of said plate and a transverse concave curvature along the transverse axis of said plate;

a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface and having a reduced diameter portion near said lower surface, a respective one of said plurality of bone screw receiving holes located at each of said rounded lobes such that said plate has a first pair of said bone screw receiving holes located at said first end of said plate corresponding to a first of the adjacent vertebrae, a second pair of said bone screw receiving holes corresponding to a second of the adjacent vertebrae, and a third pair of bone screw receiving holes corresponding to a third of the adjacent vertebrae, each of said bone screw receiving holes having an offset recess for receiving a locking element; and

a plurality of locking elements for locking a bone screw placed in said bone screw receiving hole, each of said

09613566-071700

plurality of locking elements engageable in a respective one of said offset recesses to lock a bone screw to said plate, each of said locking elements having a bottom surface and a top surface with a depression for engaging a tool used to lock and unlock said locking element to said plate, said bottom surface configured to fit over the bone screw and bear against the bone screw.

292. The plate system of claim 291 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

293. The plate system of claim 291 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

294. The plate system of claim 291 in which said plate has a length longer than said width, and said lower surface has concave curvature parallel to said length, said concave curvature having a radius of curvature greater than 15 cm and less than 25 cm.

295. The plate system of claim 291 in which said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

296. The plate system of claim 295 in which said first

concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

297. The plate system of claim 296 in which said lower surface of said plate has a second concave curvature parallel to said length.

298. The plate system of claim 297 wherein said second concave curvature has a radius of curvature greater than 15 cm and less than 25 cm.

299. An anterior cervical plate for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said plate having a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface, said plate having a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface, at least a first and second of said bone screw receiving holes being associated with a first of the cervical vertebrae, and a recess associated with said at least first and second of said bone screw receiving holes, said recess having a configuration for retaining a locking element for locking at least two bone screws in said at least first and second bone screw receiving holes, the central longitudinal axis of said recess being offset from a transverse line passing through the central longitudinal axes of said first and second bone screw receiving holes.

300. The plate of claim 299 further comprising at least a third bone screw receiving hole corresponding to the area between the first and second cervical vertebrae, and said recess being associated with said first and second bone screw receiving holes and with said third bone screw receiving hole.

301. The plate of claim 300 in which said recess overlaps a portion of said first bone screw receiving hole and said third bone screw receiving hole.

302. The plate of claim 299 in which said recess overlaps a portion of at least four bone screw receiving holes.

303. The plate of claim 299 in which said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

304. The plate of claim 303 in which said first concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

305. The plate of claim 299 in which said lower surface of said plate has a second concave curvature parallel to said length.

306. The plate of claim 305 wherein said second concave curvature has a radius of curvature greater than 15 cm and less than 25 cm.

307. The plate of claim 299 in which said plate has a length sufficient to span at least three consecutive vertebrae.

308. The plate of claim 299 in which said lower surface of said plate has a complex concave curvature configured to mate with the vertebral bodies of the at least two vertebrae, and each bone screw receiving hole has a longitudinal axis that is generally perpendicular to said lower surface at the location of said bone screw receiving hole and each of said bone screw receiving holes is formed to retain a respective bone screw in a position in which the longitudinal axis of said respective bone screw is aligned with the longitudinal axis of said bone screw receiving hole.

309. The plate of claim 299 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

310. The plate of claim 299 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

311. The plate of claim 299 in which at least a portion of said lower surface comprises a bone growth material.

312. The plate of claim 299 in which at least a portion of said lower surface comprises a bone ingrowth material.

313. The plate of claim 299 in which at least a portion of said plate is coated with a material to induce the formation

of bone.

314. The plate of claim 299 in which said plate comprises bone morphogenetic protein.

315. The plate of claim 299 in which at least a portion of said plate is made of a material which is resorbable.

316. The plate of claim 315 in which said resorbable material is polygyconate.

317. The plate of claim 315 in which said resorbable material is impregnated with a fusion promoting substance.

318. The plate of claim 299 in which at least a portion of said lower surface is textured so as to promote bone ingrowth.

319. The plate of claim 318 in which said textured portion is impregnated with a fusion promoting substance.

320. The plate of claim 299 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

321. The plate of claim 299 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

322. The plate of claim 299 in which said aperture comprises a slot along the longitudinal axis of said plate.

323. The plate of claim 299 in which at least at one end of said plate includes means for engaging a compression tool.

324. The plate of claim 323 in which said engaging

means comprises a recess.

325. The plate of claim 323 in which said engaging means comprises a depression in said at least one end of said plate.

326. An anterior cervical plate for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said plate having a length sufficient to span at least two adjacent cervical vertebrae, said plate having a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface, said plate having a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface, at least a first and second of said bone screw receiving holes being associated with a first of the cervical vertebrae, and a recess for retaining a locking element for locking bone screws in said bone screw receiving holes, said recess having a central longitudinal axis offset from a transverse line passing through the central longitudinal axes of said first and second bone screw receiving holes, and a locking element movably engageable in said recess being movable from at least a first position to a second position, said locking element being configured so as to permit insertion of bone screws into each of said first and second bone screw receiving holes when in said first position, and said head bearing against at least a portion of at least one of said bone

screws in said first and second bone screw receiving holes when moved to said second position.

327. The plate of claim 326 in which said locking element has a bearing surface for bearing against a bone screw.

328. The plate of claim 326 in which said locking element has a camming surface.

329. The plate of claim 326 in which said locking element has a ramped surface.

330. The plate of claim 326 in which said recess has a threaded portion.

331. The plate of claim 330 in which said locking element comprises a threaded portion.

332. The plate of claim 330 in which said locking element has a camming surface.

333. The plate of claim 330 in which said locking element has a ramped surface.

334. The plate of claim 330 in which said locking element comprises a screw having a head portion and a threaded shaft.

335. The plate of claim 330 in which said locking element has a camming surface.

336. The plate of claim 330 in which said locking element has a ramped surface.

337. The plate of claim 326 in which said locking

element comprises a rivet.

338. The plate of claim 337 in which said rivet has a camming surface.

339. The plate of claim 337 in which said rivet has a ramped surface.

340. The plate of claim 326 in which said recess has at least one camming surface for cooperation with said locking element.

341. The plate of claim 326 in which said head has at least one segment removed therefrom.

342. The plate of claim 341 in which said removed segment has the same or greater radius of curvature as the corresponding bone screw receiving holes.

343. The plate of claim 326 further comprising an opening in the side wall of said bone screw receiving holes in communication with the side wall of said recess, said locking element having a plurality of projections to fit within said side wall openings so as to cover a portion of said bone screw receiving hole when said locking element is moved from said first position to said second position.

344. The plate of claim 343 in which said projections have a ramped surface.

345. The plate of claim 326 in which said locking element is permanently attached to said plate.

346. The plate of claim 326 in which said locking element has at least three segments removed therefrom, each of said at least three segments corresponding to a different bone screw receiving hole whereby movement of said locking element from said first position to said second position causes said locking element to bear against at least a portion of the bone screws in said three bone screw receiving holes.

347. The plate of claim 326 in which said locking element has at least four segments removed, each of said at least four segments corresponding to a different bone screw receiving hole whereby movement of said locking element from said first position to said second position causes said locking element to bear against at least a portion of the bone screws in said four bone screw receiving holes.

348. The plate of claim 326 in which said locking element covers at least a portion said bone screw receiving hole when placed in said recess.

349. The plate of claim 326 in which said locking element covers at least a portion of one of said bone screw receiving holes.

350. The plate of claim 326 in which said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

351. The plate of claim 350 in which said first

concave curvature has a radius of curvature of the order of approximately 16-21 mm.

352. The plate of claim 326 in which said lower surface of said plate has a second concave curvature parallel to said length.

353. The plate of claim 352 in which said second concave curvature has a radius of curvature greater than approximately 15 cm and less than approximately 25 cm.

354. The plate of claim 326 in which said plate has a generally rectangular configuration with lobes extending from at least the corners of said plate and has at least one of said bone screw receiving holes located within the circumference of said lobes.

355. The plate of claim 326 in which said plate has a length sufficient to span at least three consecutive vertebrae.

356. The plate of claim 326 in which the central axes of said bone screw receiving holes are perpendicular to said lower surface of said plate.

357. The plate of claim 326 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

358. The plate of claim 326 in which the central longitudinal axes of the bone screw receiving holes of at least

one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

359. The plate of claim 326 in which at least a portion of said lower surface comprises a bone ingrowth material.

360. The plate of claim 326 in which at least a portion of said lower surface comprises a bone growth material.

361. The plate of claim 326 in which at least a portion of said plate is coated with a material to induce the formation of bone.

362. The plate of claim 326 in which said plate comprises bone morphogenetic protein.

363. The plate of claim 326 in which at least a portion of said plate is made of a material which is resorbable.

364. The plate of claim 363 in which said resorbable material is polygyconate.

365. The plate of claim 363 in which said resorbable material is impregnated with a fusion promoting substance.

366. The plate of claim 326 in which at least a portion of said lower surface is textured so as to promote bone ingrowth.

367. The plate of claim 366 in which said textured portion is impregnated with a fusion promoting substance.

368. The plate of claim 326 in which at least a portion of said lower surface comprises a time released bone growth inducing material.

002720" 9956T 960

369. The plate of claim 326 in which at least a portion of said lower surface is roughened to promote the growth of bone along said lower surface.

370. The plate of claim 326 in which at least one end of said plate has means for removably engaging a compression tool.

371. The plate of claim 370 in which said engaging means comprises a depression at least one end of said plate.

372. The plate of claim 326 in which said plate includes an opening proximate said second bone screw receiving holes associated with said second adjacent vertebrae.

373. The plate of claim 372 in which said opening comprises a slot along the longitudinal axis of said plate.

374. An anterior cervical plate for engaging at least two vertebrae of a human cervical spine along the anterior aspect of the spine, said device comprising:

a plate having a first end, a second end, and a length sufficient to span at least two adjacent cervical vertebrae, said plate having a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface, said plate having a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface, at least a first and second of said bone screw receiving holes being associated with a first of the adjacent

vertebrae, and a recess for retaining a locking element for locking bone screws in said bone screw receiving holes, said recess having a central longitudinal axis offset from a transverse line passing through the central longitudinal axes of said first and second bone screw receiving holes, and a locking element movably engageable in said recess having a head and being movable from at least a first position to a second position, said head having a configuration so as to permit insertion of bone screws into said first and said second bone screw receiving holes when in said first position, and said head bearing against a portion of the bone screws inserted into said first and said second bone screw receiving holes when moved to said second position; and

a plurality of bone screws each having a longitudinal axis and insertable into a respective one of said bone screw receiving holes in a direction from said upper surface to said lower surface to secure said plate to a vertebra.

375. The plate of claim 374 in which said locking element has a bearing surface for bearing against a bone screw.

376. The plate of claim 374 in which said locking element has a camming surface.

377. The plate of claim 374 in which said locking element has a ramped surface.

378. The plate of claim 374 in which said recess has a

threaded portion.

379. The plate of claim 378 in which said locking element comprises a threaded portion.

380. The plate of claim 378 in which said locking element has a camming surface.

381. The plate of claim 374 in which said locking element has a ramped surface.

382. The plate of claim 378 in which said locking element has a head portion and a threaded shaft.

383. The plate of claim 382 in which said locking element has a camming surface.

384. The plate of claim 382 in which said locking element has a ramped portion surface.

385. The plate of claim 382 in which said locking element is a rivet.

386. The plate of claim 385 in which said rivet has a camming surface.

387. The plate of claim 385 in which said rivet has a ramped surface.

388. The plate of claim 374 in which said recess has at least one camming surface for cooperation with said locking element.

389. The plate of claim 374 in which said locking element has at least two segments removed therefrom, said removed

segments being arcuate and have the same or greater radius of curvature than a corresponding bone screw receiving holes.

390. The plate of claim 374 further comprising an opening in the side wall of said bone screw receiving holes in communication with the side wall of said recess, said locking element having a plurality of projections to fit within said side wall openings so as to cover a portion of said first, second, and intermediate bone screw receiving holes when said locking element is moved from its first position to its second position.

391. The plate of claim 390 in which said projections have a ramped surface.

392. The plate of claim 374 in which said locking element is permanently attached to said plate.

393. The plate of claim 374 in which said locking element has at least three segments removed therefrom, each of said at least three segments corresponding to a different bone screw receiving hole whereby movement of said locking element from said first position to said second position causes said locking element to cover at least a portion of three bone screw receiving holes.

394. The plate of claim 374 in which said locking element has at least four segments removed therefrom, each of said at least four segments corresponding to a different bone screw receiving hole whereby movement of said locking element

from said first position to said second position causes said locking element to cover at least a portion of four bone screw receiving holes.

395. The plate of claim 374 in which said locking element covers at least one of said bone screw receiving holes.

396. The plate of claim 374 wherein said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

397. The plate of claim 396 wherein said first concave curvature has a first radius of curvature of approximately about 16-21 mm.

398. The plate of claim 397 wherein said lower surface of said plate has a second concave curvature parallel to said length.

399. The plate of claim 398 wherein said second concave curvature has a radius of curvature greater than approximately 15 cm and less than approximately 25 cm.

400. The plate of claim 374 in which said plate has a generally rectangular configuration, has lobes extending from at least the corners of said plate, and has at least one of said bone screw receiving holes are located within the circumference of said lobes.

401. The plate of claim 374 in which said plate has a length sufficient to span at least three consecutive vertebrae.

402. The plate of claim 374 in which the central axes of said bone screw receiving holes are perpendicular to said lower surface of said plate.

403. The plate of claim 374 further comprising a plurality of bone screws each having a head dimensioned to achieve an interference fit with a respective one of said bone screw receiving holes.

404. The plate of claim 403 in which said bone screw and said locking element have heads with means for engagement by the same tool for rotating said bone screw and said locking element.

405. The plate of claim 403 in which said bone screw has a first head with an irregular depression in the top of said first head for engagement with a screwdriver; and said locking element has a second head with an irregular depression in said second head for engagement with a screwdriver, whereby both said first and said second heads may be engaged by the same screwdriver.

406. The plate of claim 403 in which each of said bone screws is a self-tapping screw.

407. The plate of claim 403 in which each of said bone screws has a tip remote from said head, a shank which is tapered from said head to said tip, and a thread having a substantially constant crest diameter over substantially the length of said

shank.

408. The plate of claim 407 in which said thread of each of said bone screws has a thin profile and a sharp crest.

409. The plate of claim 403 in which said bone screws and said locking element do not project above the upper surface of said plate when said plate is installed.

410. The plate of claim 374 in which said recess includes a thread on the interior of said bone screw receiving hole.

411. The plate of claim 374 in which said bone screw receiving hole has means for preventing a bone screw from passing through said bone screw receiving hole.

412. The plate of claim 374 in which said bone screw receiving hole has an upper diameter portion and a smaller lower diameter portion to prevent a bone screw being placed in said bone screw receiving hole from passing through said bone screw receiving hole.

413. The plate of claim 374 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

414. The plate of claim 374 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included

angle greater than 20 degrees and less than 30 degrees.

415. The plate of claim 374 wherein at least a portion of said lower surface comprises a bone ingrowth material.

416. The plate of claim 374 in which at least a portion of said lower surface comprises a bone growth material.

417. The plate of claim 374 in which at least a portion of said plate is made of a material which is resorbable.

418. The plate of claim 417 in which said resorbable material is polygyconate.

419. The plate of claim 417 in which said resorbable material is impregnated with a fusion promoting substance.

420. The plate of claim 374 in which at least a portion of said lower surface is textured.

421. The plate of claim 420 in which said textured portion is impregnated with a fusion promoting substance.

422. The plate of claim 374 in which at least a portion of said lower surface comprises a time released bone growth material.

423. The plate of claim 374 in which at least one of said ends of said plate has means for removably engaging a compression tool.

424. The plate of claim 423 in which said engaging means comprises a depression in said at least one end of said plate.

425. The plate of claim 374 in which said plate includes an opening proximate said second bone screw receiving hole associated with said second adjacent vertebrae.

426. The plate of claim 425 in which said opening comprises a slot along the longitudinal axis of said plate.

427. An anterior cervical plating system for engaging at least three vertebrae of a human cervical spine along the anterior aspect of the spine, said device comprising:

a plate having a generally rectangular configuration with a first end, a second end, sides, and a length sufficient to span at least two adjacent cervical vertebrae, said plate having:

rounded lobes at each corner of said generally rectangular configuration and having rounded lobes on said sides between said first and second ends;

a lower surface for contacting the cervical vertebrae and an upper surface opposite to said lower surface;

a bi-concave curvature for conforming to the anterior aspect of the cervical spine in lordosis, said bi-concave curvature having a longitudinal concave curvature along the longitudinal axis of said plate and a transverse concave curvature along the transverse axis of said plate;

a plurality of bone screw receiving holes extending through said plate from said upper surface to said lower surface, a respective one of said plurality of bone screw

receiving holes located at each of said rounded lobes such that said plate has a first pair of said bone screw receiving holes located at said first end of said plate and corresponding to a first of the adjacent vertebrae, a second pair of said bone screw receiving holes corresponding to a second of the adjacent vertebrae, and a third pair of said bone screw receiving holes corresponding to a third of the adjacent vertebrae;

a locking element receiving opening positioned between said first pair of bone screw receiving holes, said locking element receiving opening surrounded by a recess in said plate concentric with said locking element receiving opening, and overlapping a portion of said first pair of bone screw receiving holes, said recess having a central longitudinal axis offset from a transverse line passing through the central longitudinal axes of said first pair of bone screw receiving holes;

a locking element positioned in said locking element receiving opening and having a head positionable within said recess, said head having a top surface with a depression for engaging a tool used to lock and unlock said locking element to said plate, said head being configured so as to permit insertion of bone screws into said bone screw receiving holes when in a first unlocked position and to bear against at least a portion of

the bone screw in said bone screw receiving holes when moved to a second locked position.

428. The plate system of claim 427 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle of greater than 14 degrees and less than 30 degrees.

429. The plate system of claim 427 in which the central longitudinal axes of the bone screw receiving holes of at least one of said pairs of bone screw receiving holes form an included angle greater than 20 degrees and less than 30 degrees.

430. The plate system of claim 427 in which said plate has a length longer than said width, and said lower surface has concave curvature parallel to said length, said concave curvature having a radius of curvature greater than 15 cm and less than 25 cm.

431. The plate system of claim 427 in which said plate has a length longer than said width, and said lower surface has a first concave curvature parallel to said width.

432. The plate system of claim 431 in which said first concave curvature has a radius of curvature in the order of approximately 16 to 21 mm.

433. The plate system of claim 432 in which said lower surface of said plate has a second concave curvature parallel to said length.

434. The plate system of claim 433 wherein said second concave curvature has a radius of curvature greater than 15 cm and less than 25 cm.

435. A method for joining adjacent vertebrae of the anterior cervical spine together with a plating system composed of a plate having a plurality of bone screw receiving holes and a plurality of bone screws each securable in a vertebra through a respective one of the bone screw receiving holes, said method comprising the steps of:

forming a pilot hole in a vertebra by driving a sharp-ended tool into the bone of the vertebra to create a pilot hole whereby the bone material displaced by said sharp-ended tool is driven into the vertebrae and not substantially removed; and

inserting a bone screw into the pilot hole through the respective bone screw receiving hole of the plate to attach the plate to the vertebrae.

436. The method of claim 435 in which said pilot hole forming step includes the sub-step of driving said sharp-ended tool to a final depth which is short of the posterior cortex of the vertebra.

437. The method of claim 436 further comprising the step of positioning the plate on the vertebra, and said step of forming the pilot hole includes the sub-step of driving the sharp-ended tool through a bone screw receiving hole in the

comprising a plate having a length sufficient for contacting the two adjacent cervical vertebrae and having a plurality of bone screw receiving holes and a plurality of bone screws each securable in a respective vertebra through a respective one of the bone screw receiving holes, said method comprising the steps of:

positioning said plate so as to align at least a transverse pair of the bone screw receiving holes with each of the adjacent vertebrae;

attaching said plate to a first of at least one of the two adjacent vertebrae;

compressing the space between two adjacent vertebrae;
and

attaching the plate to the second of the two vertebrae.

446. The method of claim 445 in which the compressing step includes:

securing an engaging post to a second vertebrae;

applying the first arm of a compression tool having a first arm and a second arm and means for moving said first and said second arm towards one another to said engaging post and said second arm to a portion of said plate attached to the first of the vertebrae; and

applying a compression force to the space between said two adjacent vertebrae by moving said first arm towards said

second arm.

447. The method of claim 446 in which said engaging post is a sharpened rod and said sharpened rod is secured to the second adjacent vertebrae by embedding the sharpened rod into the second vertebrae to a depth less than the depth of the body of the second vertebrae.

448. The method of claim 446 in which said vertebral body engaging post is driven to a final depth which is short of the posterior cortex of the respective vertebra.

449. The method of claim 446 in which the engaging post is installed through an opening in the plate intermediate the ends of the plate and alignable with the second vertebrae.

450. The method of claim 446 in which the compression tool is attached to the vertebral body engaging post and to the plate.

451. A method for compressing two adjacent vertebral bodies with a plate comprising the steps of:

engaging the plate with a first arm of a compression tool;

engaging the spine with a vertebral body penetrating member affixed to a second arm of said compression apparatus; and

utilizing said compression apparatus to shorten the distance between said first and second arms.

452. The method of claim 451 in which said plate

engaging step includes the substeps of:

engaging said first arm over a first vertebral body where said plate has been firmly attached to the first vertebral body with a pair of bone screws;

engaging said second arm over a second vertebral body; and

securing said plate to said second vertebral body with at least one bone screw following said step of shortening the distance between said first and second arms of said compression tool.

453. Apparatus for compressing a spinal disc space disposed between two adjacent vertebrae of a cervical spine, comprising:

a body;

a first arm having a first end and a second end, said first arm fixedly attached at its first end to said body;

a second arm having a first end and a second end, said second arm movably attached at its first end to said body;

means for imparting relative movement to said first and said second arms toward one another to create a compression force between said first and second arms; and

means for preventing movement of said second arm away from said first arm, said preventing means associated with said body and said second arm.

454. The apparatus of claim 453 in which the second end of at least one of said first and second arms has an opening for removably receiving an engagement device.

455. The apparatus of claim 454 in which said engaging device comprises a sharp peg.

456. The apparatus of claim 454 in which said engaging device comprises a hook.

457. The apparatus of claim 454 in which said engaging device is movable in a rotational manner and extendible along the axis of said arms.

458. The apparatus of claim 453 in which said preventing means comprises of a ratcheted member, and said imparting means for moving said arm comprises a gear associated with said second arm connected to a handle whereby rotation of said handle in a first direction moves said first arm toward said second arm.

459. The apparatus of claim 454 including a self-locking and release assembly, said self-locking and release assembly engaging said ratcheted member to prevent movement of said first and said second arms away from one another while in a first position and whereby said self-locking assembly may be disengaged from said ratchetings to a second position by operation of said release mechanism connected to said self-locking assembly.

09618566 071700

460. A pilot hole forming apparatus for creating a pilot hole in a cervical vertebral body comprising: a hollow tubular member having a top end and a lower end configured to cooperatively engage a bone screw receiving hole in a cervical plate, a rod having a sharpened-end movable within said tubular member between an upper position whereby said sharpened-end does not project beyond the lower end of said tubular member and a lower position wherein said sharpened-end projects below said lower end of said tubular member, said rod having an upper portion that extends above the upper end of said tubular member, whereby applying a force coaxial to said rod force to said upper portion of said rod drives the sharpened-end of said rod out of said tubular member, said sharpened-end having sufficient length to pass through the cervical plate and into the vertebral body to a predetermined depth less than the depth of the vertebral body.

461. The apparatus of claim 460 further comprising means for engaging the plate.

462. The apparatus of claim 460 in which said lower end of said hollow tubular member has a reduced diameter portion.

463. The apparatus of claim 462 in which said reduced diameter portion is threaded.

464. The apparatus of claim 460 in which top end of said upper end of said rod has an increased diameter portion capable of being hit by a hammer for driving the sharpened-end of

the rod into the vertebral body.

465. The apparatus of claim 460 including means for restricting the distance that said rod can extend out of said lower end of said tubular member.

466. The apparatus of claim 465 for use in the human adult cervical spine in which the distance that the rod can extend out of said lower end of said hollow tubular member is less than the depth of the vertebrae with which it is to be used.

467. The apparatus of claim 466 in which said hollow tubular member is configured to cooperatively engage a bone screw receiving hole of a spinal plate so as to form a pilot hole coaxial to the central longitudinal axis of the bone screw receiving hole.

468. The apparatus of claim 460 in which the sharpened-end of said rod has surface edges to facilitate moving bone when said rod is rotated.

469. The apparatus of claim 460 in which said sharpened-end extends from said tubular member a length of 8-20 mm.

470. The apparatus of claim 460 in which said sharpened-end has a major diameter of 2 mm.

471. A bone screw for use in attaching medical devices to the anterior aspect cervical spine vertebrae, said screw comprising a head, a shaft attached to said head and terminating

at a tip, said shaft having a thread, said shaft having a varying root diameter from proximately below said head to proximately above said tip, the outer diameter of said thread being substantially uniformly equal from proximately below said head to proximately above said tip, said thread having a thin profile and a sharp crest, said head having a transverse cross sectional dimension greater than the transverse cross sectional dimension of said shaft, and further comprising a recess for coupling to a driver instrument.

472. The bone screw of claim 471 in which said tip is sharp.

473. The bone screw of claim 471 in which said root of said shaft has an arcuate shape.

474. The bone screw of claim 471 in which said thread is of a lesser diameter at said tip than above said tip.

475. The bone screw of claim 473 in which said arcuate portion of said shaft has an increasing radius of curvature from said tip towards said head.

476. The bone screw of claim 471 in which said bone screw has a head, and said head has a convex top surface.

477. The bone screw of claim 471 in which said head has a flat portion.

478. The bone screw of claim 471 in which said head has a first upper diameter section and a smaller lower diameter

section.

479. The bone screw of claim 471 in which said head has engagement means for engagement with a screw driving tool.

480. The bone screw of claim 479 in which said engagement means is an irregular recess.

481. The bone screw of claim 471 in which said bone screw is at least in part made of a resorbable material.

482. The bone screw of claim 471 having a length of approximately 10-22 mm.

483. The bone screw of claim 482 having a thread pitch of 1.5-2.0 mm.

484. The bone screw of claim 471 in which the outer diameter of the threads is 4-5 mm.

485. A bone screw for use in human spinal surgery, said screw having a head portion, a threaded shank portion, and a tip, said threaded shank portion having a length from about 10 mm to about 22 mm and a head length from about 1 mm to about 3 mm, said threaded shank portion having a maximum outside diameter from about 3.6 mm to about 5.2 mm and said head having a diameter from about 3.8 mm to about 7.0 mm, said screw having a thread pitch from about 1.25 mm to about 2.5 mm and a sharp and thin threaded profile wherein the apex of the two faces of the thread have an angle of less than 21 degrees and the base of said thread is less than 0.5 mm thick and said screw has a root diameter that

increases from proximately above said tip along the longitudinal axis to proximately below the head portion of said screw and said thread outer diameter being generally constant from below said head portion to said tip portion.

486. The bone screw of claim 485 in which said fluting interrupts at least the most distant two thread turns at said tip.

487. The bone screw of claim 485 in which said screw has a tapered tip and at least the first thread of said tip has a diameter less than the diameter of the other screw threads.

488. The bone screw of claim 485 in which said bone screw is made of a resorbable material.

489. The bone screw of claim 485 being made of a metal suitable for human implantation.

490. The bone screw of claim 485 in which said tip being fluted by at least one cut out section so as to make said screw self-tapping.

491. A bone screw locking element for use in association with an anterior cervical plating system, said locking element comprising a member having a head, said head having a width and at least two segments removed from said head for the width of said head.

492. The bone screw locking element of claim 491 in which said member is a screw having a threaded shaft.

493. The bone screw locking element of claim 492 in which said member has a camming surface on the bottom of said head.

494. The bone screw locking element of claim 492 in which said member has a ramped surface on the bottom of said head.

495. The bone screw locking element of claim 491 in which said member comprises a rivet having a top segment and a bottom segment connected by a reduced diameter segment.

496. The bone screw locking element of claim 495 in which said rivet has a camming surface on the bottom surface of said top segment.

497. The bone screw locking element of claim 495 in which said rivet has a camming surface on the top surface of said bottom segment.

498. The bone screw locking element of claim 495 in which said rivet has a ramped surface on the bottom surface of said top segment.

499. The bone screw locking element of claim 495 in which said rivet has a ramped surface on the top surface of said bottom segment.

500. The bone screw locking element of claim 491 in which said member comprises a threaded member.

501. The bone screw locking element of claim 491 in

which said head has a camming surface.

502. The bone screw locking element of claim 491 in which said head has a ramped surface.

503. The bone screw locking element of claim 491 in which said member has at least one projection extending from said head.

504. The bone screw locking element of claim 491 in which said head has at least three removed segments.

505. The bone screw locking element of claim 491 in which said head has at least four removed segments.

506. The bone screw locking element of claim 491 in which at least a portion of said head is flexible.

507. The bone screw locking element of claim 491 in which said heads has at least one slot for providing flexibility to at least a portion of said head.

508. The bone screw locking element of claim 491 in which said removed segments are arcuate.

509. A bone screw locking element for use in association with an anterior cervical plating system comprising a member having a head, said head having a width and at least a portion of said head being flexible.

510. The bone screw locking element of claim 509 in which said head has at least one slot for providing flexibility to at least a portion of said head.

511. The bone screw locking element of claim 509 in which said member is a screw having a threaded shaft.

512. The bone screw locking element of claim 511 in which said member has a camming surface on the bottom of said head.

513. The bone screw locking element of claim 511 in which said member has a ramped surface on the bottom of said head.

514. The bone screw locking element of claim 509 in which member comprises a rivet having a top segment and a bottom segment connected by a reduced diameter segment.

515. The bone screw locking element of claim 514 in which said rivet has a camming surface on the bottom surface of said top segment.

516. The bone screw locking element of claim 514 in which said rivet has a camming surface on the top surface of said bottom segment.

517. The bone screw locking element of claim 514 in which said rivet has a ramped surface on the bottom surface of said top segment.

518. The bone screw locking element of claim 514 in which said rivet has a ramped surface on the top surface of said bottom segment.

519. The bone screw locking element of claim 509 in

which said member comprises a set screw.

520. The bone screw locking element of claim 514 in which said set screw has a camming surface.

521. The bone screw locking element of claim 509 in which said set screw has a ramped surface.

522. The bone screw locking element of claim 518 in which said member has at least one projection extending from said head.

523. The bone screw locking element of claim 509 in which said head has at least one removed segment.

524. The bone screw locking element of claim 509 in which said head has at least two removed segments.

525. The bone screw locking element of claim 509 in which said head has at least three removed segments.

526. The bone screw locking element of claim 509 in which said head has at least four removed segments.

527. A locking element for use in association with an anterior plating system comprising a member having a head, said head having a width and at least a portion of the bottom surface of said head being non uniform.

528. The locking element of claim 527 in which the bottom surface of said member has a camming surface.

529. The locking element of claim 527 in which the bottom surface of said member has a ramped surface.

530. The locking element of claim 529 in which the member is a set screw.

531. The locking element of claim 529 in which the member is a rivet.

532. The locking element of claim 529 in which the member has projections.

533. The locking element of claim 529 in which the member is a screw.

534. The locking element of claim 529 in which the member is a set screw.

535. The locking element of claim 529 in which the member is a rivet.









536. The locking element of claim 529 in which the member has projections.

537. The locking element of claim 529 in which the member is a screw.

ABSTRACT OF THE DISCLOSURE

Anatomically contoured anterior cervical plates with bone ingrowth surfaces, providing for intersegmental compressive preloading, and a rigid and locked interface to all of the bone screws, with those engaging the vertebrae deployed in highly convergent pairs. The bone screws have a tapered self-tapping leading end, an increasing root diameter with a generally constant outer diameter with a thread that is narrow and sharp throughout and an enlarged head portion capable of an interference fit to the receiving holes of the plate. Instrumentation consists of plate holders, a compression apparatus and a pilot hole forming device that interlocks with the plate. Methods for spinal compression and bone hole preparation are provided.

09548568-074700






FIG 9




FIG 15




FIG 10




FIG 11




FIG 16




FIG 12



FIG 13




FIG 17




FIG 14




FIG 18

00618566.071700

3/20




FIG 19




FIG 23




FIG 20




FIG 24A




FIG 25




FIG 21




FIG 26




FIG 22




FIG 27

4/20




FIG 24B




FIG 28




FIG 29







FIG 30






FIG 34




FIG 35




FIG 36




FIG 37








FIG 38






FIG 43




FIG 45




FIG 44










FIG 46






FIG 53




FIG 54




FIG 55




FIG 56




FIG 57




FIG 58











FIG 59








FIG 68




FIG 69A




FIG 67











FIG 69B










FIG 76




FIG 78




FIG 77




FIG 79

002720 9958T950




FIG 80





FIG 81

19/20



004720" 9998F960




FIG 83




FIG 84 A




FIG 84 B




FIG 84 C




FIG 84 D




FIG 84 E

002720998T960

DECLARATION AND POWER OF ATTORNEY FOR PATENT APPLICATION

English Language Declaration

As a below named Inventor, I hereby declare that:

My residence, post office address, and citizenship are as stated below next to my name,

I believe I am the original, first, and sole inventor (if only one name is listed below) or an original, first, and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the inventive design entitled

ANTERIOR CERVICAL PLATING SYSTEM, INSTRUMENTATION,
AND METHOD OF INSTALLATION

the specification of which

(mark one)

XXX is attached hereto or enclosed herewith.

_____ was filed on _____ as

Application Serial No. _____

and was amended on _____
(if applicable)

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose Information which is material to patentability as defined in Title 37, Code of Federal Regulations, § 1.56.

I hereby claim foreign priority benefits under Title 35, United States Code, § 119 or § 172 of any foreign application(s) for patent or Inventor's certificate listed below and have also identified below any foreign application for patent or Inventor's certificate having a filing date before that of the application on which priority is claimed:

002720-9958960

Priority Claimed

<u>(Number)</u>	<u>(Country)</u>	<u>(Day/Month/Year Filed)</u>	<u>Yes</u>	<u>No</u>
-----------------	------------------	-------------------------------	------------	-----------

I hereby claim the benefit under Title 35, United States Code, §119(e) of any United States Provisional application(s) listed below:

Application No. 60/037,139
Filing Date: February 11, 1997

I hereby claim the benefit under Title 35, United States Code, § 120 of any United States application(s) listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States application in the manner provided by the first paragraph of Title 35, United States Code, § 112, I acknowledge the duty to disclose information material to patentability as defined in Title 37, Code of Federal Regulations, § 1.56(a) which became available between the filing date of the prior application and the national or PCT International filing date of this application:

(Application Serial No.)	(Filing Date)	(Status: patented, pending, abandoned, etc.)
1	1950	patented
2	1951	pending
3	1952	abandoned
4	1953	patented
5	1954	pending
6	1955	abandoned
7	1956	patented
8	1957	pending
9	1958	abandoned
10	1959	patented
11	1960	pending
12	1961	abandoned
13	1962	patented
14	1963	pending
15	1964	abandoned
16	1965	patented
17	1966	pending
18	1967	abandoned
19	1968	patented
20	1969	pending
21	1970	abandoned
22	1971	patented
23	1972	pending
24	1973	abandoned
25	1974	patented
26	1975	pending
27	1976	abandoned
28	1977	patented
29	1978	pending
30	1979	abandoned
31	1980	patented
32	1981	pending
33	1982	abandoned
34	1983	patented
35	1984	pending
36	1985	abandoned
37	1986	patented
38	1987	pending
39	1988	abandoned
40	1989	patented
41	1990	pending
42	1991	abandoned
43	1992	patented
44	1993	pending
45	1994	abandoned
46	1995	patented
47	1996	pending
48	1997	abandoned
49	1998	patented
50	1999	pending
51	2000	abandoned
52	2001	patented
53	2002	pending
54	2003	abandoned
55	2004	patented
56	2005	pending
57	2006	abandoned
58	2007	patented
59	2008	pending
60	2009	abandoned
61	2010	patented
62	2011	pending
63	2012	abandoned
64	2013	patented
65	2014	pending
66	2015	abandoned
67	2016	patented
68	2017	pending
69	2018	abandoned
70	2019	patented
71	2020	pending
72	2021	abandoned
73	2022	patented
74	2023	pending
75	2024	abandoned
76	2025	patented
77	2026	pending
78	2027	abandoned
79	2028	patented
80	2029	pending
81	2030	abandoned
82	2031	patented
83	2032	pending
84	2033	abandoned
85	2034	patented
86	2035	pending
87	2036	abandoned
88	2037	patented
89	2038	pending
90	2039	abandoned
91	2040	patented
92	2041	pending
93	2042	abandoned
94	2043	patented
95	2044	pending
96	2045	abandoned
97	2046	patented
98	2047	pending
99	2048	abandoned
100	2049	patented

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.


POWER OF ATTORNEY: As a named inventor, I hereby appoint **Lewis Anten, Registration Number 26,604 and Amedeo Ferraro, Registration Number 37,129** to prosecute this application and transact all business in the Patent and Trademark Office connected therewith. Please send all correspondence, transmit all faxes, and direct all telephone calls to:

Lewis Anten, Reg. No. 26,604
Law Offices of Lewis Anten, P.C.
Attorneys for Applicant
Suite 411
16830 Ventura Boulevard
Encino, California 91436

Tel: (818) 501-3535
Fax: (818) 501-3618

Gary K. Michelson, M.D.

Full name of sole inventor



Inventor's signature

2/10/98

Date

438 Sherman Canal, Venice, CA 90291

Residence

USA

Citizenship

438 Sherman Canal, Venice, CA 90291

Post Office Address (where mail customarily received)

09618566-07100
002720-99987960

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of:)
)
Gary K. Michelson)
)
Serial No.: (Div. of 09/022,293)) (Group Art Unit: 3731)
)
Filed: July 17, 2000) (Examiner: D. Reip)
)
For: Anterior Cervical Plating System,)
Instrumentation, and Method of)
Installation)

Assistant Commissioner for Patents
Washington, D.C. 20231

Sir:

**REVOCATION OF ORIGINAL POWER OF ATTORNEY
AND GRANT OF NEW POWER OF ATTORNEY**

Applicant Gary K. Michelson hereby revokes the previous Power of Attorney
in the above action to Lewis Anten, Registration No. 26,604


09618566-07100

and hereby grants his power of attorney to **MARTIN & FERRARO, LLP**, Thomas H. Martin, Reg. No. 34,383; Amedeo F. Ferraro, Reg. No. 37,129; and Todd M. Martin, Reg. No. 42,844; both jointly and separately as his attorneys with full power of substitution and revocation to prosecute this application, and all divisions, and continuations thereof, and all Letters Patent of the United States which may be granted thereon, and all reissues thereof, and to transact all business in the Patent and Trademark Office connected therewith, and to receive the Letters Patent.

Please send all future correspondence concerning this application to Martin & Ferraro, LLP at the following address:

Customer ID # 22882
Martin & Ferraro, LLP
14500 Avion Parkway, Suite 300
Chantilly, Virginia 20151-1101
Telephone: (703) 679-9300
Facsimile: (703) 679-9303

Date: July 17, 2000



Gary K. Michelson

05645566.07700